

Al Saints Junior School, Brownlow Road, Reading, RG1 6NP

Proposed Works by Equazion Limited

1. Replacing the main Front Door, leading from the reception lobby to the arched external exit porch
2. Solid Timber Door - Fire Rated Solid Timber Door
3. New Solid timber door will have the same profile as the existing and will be inset into the existing frame
4. The new Solid timber front door will be decorated to match the existing door colour.

Current Main Front Door



Assuming works are carried out during normal working hours

- Pre site attendance RAMS will be supplied
- Pre-site attendance, we will attend site and take measurements of the existing front door and door frame to allow the new solid timber oversized front door to be factory cut to near installation size
- Check that RAMS have not changed
- Set barriers as required
- Disassemble and remove existing front door
- Supply and install new solid timber fire rated front door into existing frame, making minor size adjustments as required
- Remove and install intumescent strip to new front door
- Re-install and adjust the new front door into position, cutting in locks and new door closer
- Paint the new door in a Gloss weatherproof colour