

Scope of Works

| Tree Group<br>Hedge or<br>Shrub No. | SPECIES | ARBORICULTURISTS OBSERVATIONS                                                                                                                                                                                                                                                                                                                                                                                                                                       | RECOMMENDED WORKS REQUIRING APPROVAL                                                                                                                                                                                                                                                                                                                                          | TPO Ref   |
|-------------------------------------|---------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------|
| T8                                  | Lime    | Ivy present with limited physical access due to lock island weir side wall.<br>Epicormic basal growth and up trunk to approx 4m.<br>Evidence of previous pruning works.<br>Low branches over weir north-western side.<br>Potential cavities at site of previous pruning, unable to ascertain extent.<br>Moderate deadwood over public footpath.<br>Low branch growing towards services pole to south.<br>See picture for site of wounding to be climbing inspected. | Remove basal epicormic and epicormic growth up to approx 3m to maintain clearance over footpath to southwest and weir side lock island wall.<br>Climbing Inspection of potential cavities on weir side. Maintain clearance of low southern branch by removing up to 3m of lateral growth.<br>Remove moderate deadwood observed over footpath to reduce likelihood of failure. | 101-06 T1 |
| T10                                 | Ash     | Ivy present from base to crown break<br>Sparsely foliated upper crown, declining vitality. Lower crown area appears to have reasonable vitality.<br>Minor deadwood observed throughout upper crown as a result of localised die back.                                                                                                                                                                                                                               | Retrenchment prune by approx 4m. This pruning should focus on height removal of declining foliage area, being mindful to leave as much conductive foliage area in lower crown to aid with potential recovery.<br>At time of pruning, assess for signs of ADB.<br>Monitor in summer 2022 for ADB & any further decline in vitality.                                            | 101-06 T3 |