

Planting Schedule : SHRN-LDA-S2-ZZ-DR-L-300-105

Trees						
Number	Species	Specification	Girth	Height	Pot Size	Density
1 No.	Acer ginnala	Multi-stem :3 Stems min. :5x :RB		450-500cm		Counted
3 No.	Betula pubescens	3x; Multi-stem; bushy; 3 stems minimum :RB		350-400cm		Counted
1 No.	Quercus castaneifolia	Semi-mature; clear stem minimum 200cm	30-35cm	600-650cm	350-500L	Counted
Total :5 No.						

Shrubs						
Number	Species	Specification	Height	Diameter	Pot Size	Density
2 No.	Viburnum burkwoodii	Multi-stem :Branched :5/7 brks : Crown lifted to 1.2-1.5m	175-200cm		70-90L	Counted
Total :2 No.						

Herbaceous				
Number	Species	Specification	Pot Size	Density
54 No.	Anemone hupehensis 'September Charm'	Full Pot	2L	7/m²
63 No.	Aster divaricatus	Full Pot	2L	7/m²
78 No.	Aster macrophyllus 'Twilight'	Full Pot	2L	7/m²
63 No.	Astrantia major 'Roma'	Full Pot	2L	7/m²
66 No.	Bergenia 'Abendglut'	Full Pot	2L	9/m²
81 No.	Epimedium × perralchicum 'Fröhnleiten'	Full Pot	2L	9/m²
146 No.	Euphorbia amygdaloides robbiae	Full Pot	2L	9/m²
63 No.	Geranium phaeum 'Lilly Lovell'	Full Pot	2L	7/m²
63 No.	Heuchera 'Obsidian'	Full Pot	2L	7/m²
80 No.	Tricyrtis formosana	Full Pot	2L	9/m²
Total :757 No.				

Climbers					
Number	Species	Specification	Height	Pot Size	Density
2 No.	Clematis armandii	Caned :Several Shoots :3 brks	150-200cm	15-20L	Counted
2 No.	Clematis cirrhosa 'Freckles'	Caned :Several Shoots :3 brks	100-150cm	10L	Counted
4 No.	Hedera helix 'Maple Leaf'	Caned :Several Shoots :5 brks	150-200cm	10L	Counted
4 No.	Hydrangea anomala subsp. petiolaris	Caned :7 brks :Several Shoots	100-150cm	15-20L	Counted
Total :12 No.					

Ferns				
Number	Species	Specification	Pot Size	Density
46 No.	Dryopteris wallichiana	Full Pot	5-7.5L	5/m²
97 No.	Polypodium vulgare	Full Pot	2L	11/m²
31 No.	Polystichum setiferum 'Herrenhausen'	Full Pot	5L	4/m²
Total :174 No.				

Grasses				
Number	Species	Specification	Pot Size	Density
63 No.	Carex divulsa	Full Pot	2L	7/m²
80 No.	Hakonechloa macra	Full Pot	2L	9/m²
21 No.	Anemanthele lessoniana	Full Pot	5-7.5L	3/m²
66 No.	Deschampsia flexuosa	Full Pot	2L	6/m²
54 No.	Luzula nivea	Full Pot	2L	7/m²
Total :284 No.				

Planting Schedule : SHRN-LDA-S2-ZZ-DR-L-300-106

Trees						
Number	Species	Specification	Girth	Height	Pot Size	Dens
1 No.	Acer campestre 'Red Shine'	5x; Semi-mature; clear stem minimum 200cm :RB	35-40cm	600-650cm		Coun
3 No.	Betula pendula	3x; Multi-stem; bushy; 3 stems minimum :RB		350-400cm		Coun
2 No.	Betula pendula 'Zwitsers Glorie'	4x; Semi-mature; clear stem minimum 200cm :RB	35-40cm	500-550cm		Coun
2 No.	Liquidambar styraciflua 'Worplesdon'	5x; Semi-mature; clear stem minimum 200cm :RB		35-40cm	600-650cm	Coun
1 No.	Pyrus calleryana 'Chanticleer'	4x; Semi-mature; clear stem minimum 200cm :RB	35-40cm	600-700cm		Coun
1 No.	Quercus ilex	3x; Extra Heavy Standard; clear stem 175-200cm; 5 breaks :RB	14-16cm	425-600cm		Coun
Total :10 No.						

Shrubs						
Number	Species	Specification	Height	Diameter	Pot Size	Density
42 No.	Euonymus fortunei 'Dart's Blanket'	Bushy :5/6 brks		30-40cm	3L	5/m²
44 No.	Pachysandra terminalis	Several shoots :7 brks		15-20cm	2L	11/m²
3 No.	Viburnum burkwoodii	Multi-stem :Branched :5/7 brks : Crown lifted to 1.2-1.5m	175-200cm		70-90L	Counted
Total :89 No.						

Herbaceous				
Number	Species	Specification	Pot Size	Density
10 No.	Anemone hupehensis 'September Charm'	Full Pot	2L	7/m²
13 No.	Aquilegia vulgaris var. stellata 'Blue Barlow'	Full Pot	2L	9/m²
31 No.	Aster divaricatus	Full Pot	2L	7/m²
16 No.	Aster macrophyllus 'Twilight'	Full Pot	2L	7/m²
22 No.	Astrantia major 'Roma'	Full Pot	2L	7/m²
19 No.	Bergenia 'Silberlicht'	Full Pot	2L	9/m²
24 No.	Epimedium × perralchicum 'Fröhnleiten'	Full Pot	2L	9/m²
59 No.	Erigeron karvinskianus	Full Pot	2L	11/m²
93 No.	Euphorbia amygdaloides robbiae	Full Pot	2L	9/m²
42 No.	Geranium endressii 'Wargrave Pink'	Full Pot	2L	7/m²
34 No.	Geranium Rozanne	Full Pot	2L	7/m²
15 No.	Heuchera 'Obsidian'	Full Pot	2L	7/m²
18 No.	Phlomis russeliana	Full Pot	2L	5/m²
13 No.	Selinum wallichianum	Full Pot	2L	6/m²
Total :409 No.				

Climbers					
Number	Species	Specification	Height	Pot Size	Density
2 No.	Clematis armandii	Caned :Several Shoots :3 brks	150-200cm	15-20L	Counted
4 No.	Clematis cirrhosa 'Freckles'	Caned :Several Shoots :3 brks	100-150cm	10L	Counted
2 No.	Hedera helix 'Maple Leaf'	Caned :Several Shoots :5 brks	150-200cm	10L	Counted
4 No.	Hydrangea anomala subsp. petiolaris	Caned :7 brks :Several Shoots	100-150cm	15-20L	Counted
Total :12 No.					

Bulbs			
Number	Species	Bulb Size	Density
171 No.	Allium christophii	12/14	7/m²
Total :171 No.			

Ferns				
Number	Species	Specification	Pot Size	Density
64 No.	Polypodium vulgare	Full Pot	2L	11/m²
Total :64 No.				

Grasses				
Number	Species	Specification	Pot Size	Density
29 No.	Carex divulsa	Full Pot	2L	7/m²
42 No.	Sesleria autumnalis	Full Pot	2L	7/m²
79 No.	Luzula nivea	Full Pot	2L	7/m²
14 No.	Molinia caerulea subsp. caerulea 'Heidebraut'	Full Pot	2L	5/m²
19 No.	Melica uniflora 'Alba'	Full Pot	2L	9/m²
25 No.	Stipa tenuissima	Full Pot	2L	9/m²
9 No.	Deschampsia flexuosa	Full Pot	2L	6/m²
24 No.	Hakonechloa macra	Full Pot	2L	9/m²
Total :241 No.				

Planting Schedule : SHRN-LDA-S2-ZZ-DR-L-300-107

Trees						
Number	Species	Specification	Girth	Height	Pot Size	Density
2 No.	Betula pendula 'Zwitsers Glorie'	4x; Semi-mature; clear stem minimum 200cm :RB	35-40cm	500-550cm		Counted
3 No.	Pyrus calleryana 'Chanticleer'	4x; Semi-mature; clear stem minimum 200cm :RB	35-40cm	600-700cm		Counted
Total :5 No.						

Shrubs						
Number	Species	Specification	Height	Diameter	Pot Size	Density
4 No.	Euonymus fortunei 'Dart's Blanket'	Bushy :5/6 brks		30-40cm	3L	5/m²
Total :4 No.						

Herbaceous				
Number	Species	Specification	Pot Size	Density
6 No.	Geranium Rozanne	Full Pot	2L	7/m²
4 No.	Phlomis russeliana	Full Pot	2L	5/m²
Total :10 No.				

Grasses				
Number	Species	Specification	Pot Size	Density
6 No.	Luzula nivea	Full Pot	2L	7/m²
Total :6 No.				

READ THIS FIRST

- Note for Contractors**

This drawing should be considered along with the risk information contained in the CDM Pre Construction Information. This information will include details of the SIGNIFICANT risks which LDA Design has identified which may arise from constructing their designs shown on this drawing. A Competent Contractor should be aware of the typical risks associated with doing this work.
- Note for Workers**

DO NOT START YOUR WORK unless you know the Risks and Controls relating to the work on this drawing (including SAFE SEQUENCES OF WORK and EQUIPMENT).
- Do not issue copies of parts of this drawing without the above Note for Workers (unless you are sure that the Workers can undertake the work safely).

T03	STAGE 4a ISSUE	CI	29/03/21
T02	STAGE 4a ISSUE	CI	03/07/20
T01	STAGE 4a ISSUE	CI	05/06/20
REV.	DESCRIPTION	APP.	DATE

LDA DESIGN

PROJECT TITLE
STATION HILL NORTH, READING

DRAWING TITLE
PHASE 2 PLANTING SCHEDULES
SHEET 2 OF 2

ISSUED BY	London	T: 020 7467 1470
DATE	05/06/2020	DRAWN BR
SCALE@/A1	Not to scale	CHECKED TW
STATUS	Tender	APPROVED CI

DWG. NO SHRN-LDA-S2-ZZ-DR-L-300-109

No dimensions are to be scaled from this drawing.
All dimensions are to be checked on site.
Area measurements for indicative purposes only.
© LDA Design Consulting Ltd. Quality Assured to BS EN ISO 9001 : 2015
Sources Ordnance Survey

Not to scale

