

Tree survey ref No.	TPO ref No.	Species	Approved work
OBDD	T16	Yew	No work required
OBDE	T17	Yew	Crown lift to 2-2.5m above the parking space on east side of tree
OBDF	T18	Yew	No work required
OB DG	T19	Yew	Reduce lower branches to give 1m horizontal clearance from the footpath on the north & east side
OB DJ	T1	Sycamore	No works required
OB DK	T2	Ash	No work required
OB DL	T3	Sycamore	No work required
OB DP	T14	Western red cedar	Crown lift to 5.5m over road by removing tertiary growth
OB DT	T13	False cypress	Crown lift to 2.5m through 360° removing minor growth only but including one low, curved limb on west side
OB DW	T12	Willow	No works required (2-3m high monolith)
OB DX	T11	Willow	Crown reduce all over by 2-3m (ensuring no more than one third of the foliage of each branch is removed); remove two low secondary branches on south side
OB ET, OB EU, OB EV	G4	Maple	Remove dead wood and also squirrel damaged branches if considered dangerous
OB F0	G3	Lime	Crown lift to 4m through 360° by removing minor and epicormic growth; remove 3 small branches over the garden of 5 Woodford Close and reduce branches overhanging this garden back to fork (see photos)

Tree survey ref No.	TPO ref No.	Species	Approved work
OBF1	G3	Lime	Crown lift to 4m through 360° by removing minor and epicormic growth
OBF2	G3	Lime	Crown lift to 4m through 360° by removing minor and epicormic growth
OBF3	G3	Lime	Crown lift to 4m through 360° by removing minor and epicormic growth
OBF4	G3	Lime	Crown lift to 4m through 360° by removing minor and epicormic growth
OBF5	G3	Lime	Crown lift to 4m through 360° by removing minor and epicormic growth
OBF6	G2	Horse Chestnut	Crown lift to 2m above fence height removing epicormic growth only but including one small main branch overhanging Regency Heights garden (see photos)
OBF7	G2	Lime	Crown lift to 4m through 360° by removing minor and epicormic growth; reduce branches overhanging 9 Woodford Close garden by 2-3m (see photos)
OBF8	G2	Lime	Crown lift to 4m through 360° by removing minor and epicormic growth; remove crossing/rubbing branches; reduce branches overhanging 9 Woodford Close garden by approx. 2m (see photos)

Tree survey ref No.	TPO ref No.	Species	Approved work
OBF9	T10	Lime	Reduce height by approx. 2m
OBFA	T9	Lime	Crown lift to 5m through 360°
OBH2	T8	Pine	No work required
OBH3	T7	Lime	Crown lift to first main branch overhanging Regency Heights (see photo)
OBH4	T6	Lime	Crown lift up to the stub on north side, include growth from this (see photo)
OBH5	T5	Pine	No work required
OBH9	T4	Sycamore	Crown lift to 5.5m over the road and 2.5m over the neighbours but including removal of one low branch parallel with fence (see photo)
OBH8	G1	Sycamore	Northern tree – remove one small, main leaning stem over the road (see photo) leaving stump to avoid introducing decay into base of multi-stem tree

Notes

- Removal of dead wood - this is required on the majority of trees. It is not included within the above table as approval is not required for this work however the intention to remove dead wood is noted and is prudent
- Removal / severing of Ivy - the need for this was noted on a number of trees. It is not included within the above table as approval is not required for this work however the intention to remove dead wood is noted and is prudent
- Further investigations - where the tree survey suggests further investigation, e.g. a climbing inspection, this should be carried out. Any further works identified from this, other than removal of dead or imminently dangerous branches, will require a further tree works application
- Monitoring - all trees should be monitored, but this is particularly prudent for OBH%/T5 Pine, OBH2/T8 Pine, OBDX/T11 Willow and OBF6/G2 Horse chestnut
- Where reference to photos is made, please refer to separate annotated photos to clarify the works

Regency Heights, 15/04/21 (app ref 210384)