

Greyfriars Church, Reading

External Works Finishes Schedule

External paving to link between new extension and church Hall, and internal courtyard

Marshall's Saxon textured slabs 600x900 generally, 450x450 to the steps and 600x600 to the inner courtyard, colour: Natural



New paving from Friars Street entrances

Marshall's Appleton Yorkstone Setts



Car park delineation/bump stops

Marshall's Tegular Kerb setts – colour: Pennant Grey



General driveway kerbs

Marshall's half battered concrete kerbs



Greyfriars Church, Reading

External Works Finishes Schedule

Paving delineation to
turfed areas

Marshalls concrete square edging



shutterstock.com • 657555160

Paving to Building
delineation

Ketley Staffordshire Blue pavers



Car Park Bollards

Autopa DDA100 with a white reflective band (not orange as shown in the image below)



Cycle racks and covers

Broxap Sheffield cycle racks and covers in Stainless Steel

Greyfriars Church, Reading

External Works Finishes Schedule



Vehicle gate

Jacksons Sentry cantilevered sliding gate – 1m high – PPC RAL7024



Pedestrian gates

Similar to Jacksons Barbican gates but bespoke design as shown on drawing GRE-4 921

Rainwater discharge

ACO Hexdrain channels



Balustrading to banked area walls and steps

Aluminium handrails and balusters – both in RAL7024



Greyfriars Church, Reading

External Works Finishes Schedule

Coping stones

Twice weathered concrete coping stones



Soft Landscaping

See drawings GRE-4 950 & 951

Tarmac surface to the
car parking areas

Tarmac with white line painting

