

Blakes Lock Sewage Pumping Station

Schedule of Works

14th July 2020

Table 1 below sets out the schedule of works proposed at Blakes Lock Pumping Station and should be read alongside the drawing numbers 218.3.020, 218.03.021 and 218.03.022.

Window/Door Reference	Works Proposed
WF01	WF01 to be replaced with purpose made timber frame window/sash, as per existing details. Ironmongery to be retained where possible. Paint finish to match existing
WF02	WF02 to be retained. Repairs to existing window to carried out inclusive of renewing glazing/putty decoration as per existing and minor repairs to concrete surrounds to match previous finishes
WG01	WG01 to be retained. Repairs to existing window to carried out inclusive of renewing glazing/putty decoration as per existing and minor repairs to concrete surrounds to match previous finishes
WG02	WG02 to be retained. Repairs to existing window to carried out inclusive of renewing glazing/putty decoration as per existing and minor repairs to concrete surrounds to match previous finishes
WG03	WG03 to be retained. Repairs to existing window to carried out inclusive of renewing glazing/putty decoration as per existing and minor repairs to concrete surrounds to match previous finishes
WG04	WG04 to be replaced with purpose made timber frame window/sash, as per existing details. Ironmongery to be retained where possible. Paint finish to match existing
WG05	WG05 to be replaced with purpose made timber frame window/sash, as per existing details. Ironmongery to be retained where possible. Paint finish to match existing
WG06	WG06 to be retained. Repairs to existing window to carried out inclusive of renewing glazing/putty decoration as per existing and minor repairs to concrete surrounds to match previous finishes
WG07	WG07 to be replaced with purpose made timber frame window/sash, as per existing details. Ironmongery to be retained where possible. Paint finish to match existing
WG08	WG08 to be replaced with purpose made timber frame window/sash, as per existing details. Ironmongery to be retained where possible. Paint finish to match existing
WG09	WG09 to be retained. Repairs to existing window to carried out inclusive of renewing glazing/putty decoration as per existing

	and minor repairs to concrete surrounds to match previous finishes
WG10	WG10 to be retained. Repairs to existing window to carried out inclusive of renewing glazing/putty decoration as per existing and minor repairs to concrete surrounds to match previous finishes
WG11	WG11 to be retained. Repairs to existing window to carried out inclusive of renewing glazing/putty decoration as per existing and minor repairs to concrete surrounds to match previous finishes
WG12	WG12 to be retained. Repairs to existing window to carried out inclusive of renewing glazing/putty decoration as per existing and minor repairs to concrete surrounds to match previous finishes
WG13	WG13 to be retained. Repairs to existing window to carried out inclusive of renewing glazing/putty decoration as per existing and minor repairs to concrete surrounds to match previous finishes
DG01	DG01 to be replaced with purpose made timber doorset/frame as per existing details. Ironmongery to be retained where possible. Paint finish to match existing
DG02	DG02 to be replaced with purpose made timber doorset/frame as per existing details. Ironmongery to be retained where possible. Paint finish to match existing
DG03	DG03 to be replaced with purpose made timber doorset/frame as per existing details. Ironmongery to be retained where possible. Paint finish to match existing

Table 1: Schedule of Works