

APPENDIX 5



Plate 1: Tesco Superstore car parking and access road



Plate 2: The Meadow looking from Tesco Car Park

 Offices throughout the UK and continental Europe. www.peterbrett.com	Client READING BOROUGH COUNCIL HIGHWAYS AND TRANSPORT DEPARTMENT	EAST READING MASS RAPID TRANSIT SCHEME SITE LOCATION PLAN	Date	13.07.2016
			A4 Scale	nts
			Drawn by	az
			Checked by	az
			Revision	0
		FIGURE a		



Plate 3: The Meadow



Plate 4: View from the Thames Towing Path to The Meadow



Offices throughout the UK and
 continental Europe.
www.peterbrett.com

Client

READING BOROUGH
 COUNCIL HIGHWAYS AND
 TRANSPORT DEPARTMENT

EAST READING MASS RAPID
 TRANSIT SCHEME

SITE LOCATION PLAN

Date	13.07.2016
A4 Scale	nts
Drawn by	az
Checked by	az
Revision	0
FIGURE b	



Plate 5: The River Kennet looking from west to east



Plate 6: The pedestrian and railway bridge crossing over the River Kennet


 Offices throughout the UK and
 continental Europe.
www.peterbrett.com

Client
 READING BOROUGH
 COUNCIL HIGHWAYS AND
 TRANSPORT DEPARTMENT

EAST READING MASS RAPID
 TRANSIT SCHEME

SITE LOCATION PLAN

Date	13.07.2016
A4 Scale	nts
Drawn by	az
Checked by	az
Revision	0

FIGURE c



Plate 7: The land to the south of the River Thames with the railway embankment to the south



Plate 8: The land to the south of the River Thames looking to the east

 Offices throughout the UK and continental Europe. www.peterbrett.com	Client READING BOROUGH COUNCIL HIGHWAYS AND TRANSPORT DEPARTMENT	EAST READING MASS RAPID TRANSIT SCHEME SITE LOCATION PLAN	Date	13.07.2016
			A4 Scale	nts
			Drawn by	az
			Checked by	az
			Revision	0
			FIGURE d	



Plate 9: Land at Broken Brow



Plate 10: Disused compound off the A3290 roundabout



Offices throughout the UK and
continental Europe.
www.peterbrett.com

Client
READING BOROUGH
COUNCIL HIGHWAYS AND
TRANSPORT DEPARTMENT

EAST READING MASS RAPID
TRANSIT SCHEME

SITE LOCATION PLAN

Date	13.07.2016
A4 Scale	nts
Drawn by	az
Checked by	az
Revision	0

FIGURE e

APPENDIX 6

BGS Reference: SU77SW308
British National Grid:

SU 77 SW 308 [7220 7386]

Contract: Reading Cross Town Stage II				Borehole No. 12				
Client: Berkshire County Council				Sheet No. 1 of 2 Depth 0 to 10 metres.				
Equipment and Methods Light Cable Percussion Boring 150mm Diameter		Ground Level : 36.40 m.O.D. Coordinates :		Job Number : S39/655 Location : Dates : 2/10/89 3/10/89				
Orientation : Vertical								
Daily Prog.	Water Levels	Remarks	In Situ Tests	Samples Taken	Depth (Thick)	Reduced Level	Description	Legend
				B 372 J 373 B 274 J 375	(0.40) 0.40	36.00	MADE GROUND (very stiff dark brown silty CLAY with occasional gravel)	
	2/10 3/10 2/10	Water level rose to 1.00m in 20 minutes	S 20	J 376	1.50 (0.50)	34.90	Soft brown and grey silty CLAY with subangular gravel	
			C 43	W 378	2.00	34.40	Medium dark brown slightly clayey coarse to fine SAND and GRAVEL	
			C 35	B 379 J 380			Dense to very dense brown coarse to fine sandy coarse to fine subangular to subrounded GRAVEL	
			C 42	B 381 J 382	(5.00)			
			C 52	W 383				
	2/10 2/10		C 47	B 385 J 386				
				B 387 J 388 U 389	7.00	29.40	Stiff white rubbly CHALK with some remoulded chalk becomes rubbly occasional flints (Grade IV becomes Grade III)	
				J 390 J 391				
				B 392 J 393 J 394	(3.30)			
	3/10		S 23	J 395 J 396 B 397	10.00			
			Continued					
Operator JC		General Remarks: Pit dug to avoid services					Appendix 1	
Scale 10m/sheet							Sheet No. 50	

[illegible]

BGS Reference: SU77SW309
British National Grid:

SU 77 SW 309 [7282 7383]

Contract: Reading Cross Town Stage II				Borehole No. 13			
Client: Berkshire County Council				Sheet No. 1 of 1 Depth 0 to 10 metres			
Equipment and Methods Light Cable Percussion Boring 150mm Diameter		Ground Level : 37.50 m.O.D. Coordinates :		Job Number : 539/655 Location : Dates : 25/9/89 26/9/89			
Orientation : Vertical							
Daily Prog.	Water Levels	Remarks	In Situ Tests	Samples Taken	Depth (thick)	Reduced Level	Description
				B 773	0.00	G.L.	MADE GROUND (topsoil with ash and flints)
				J 774	1.80		
			S 6	J 775	1.00	35.70	
				U 776	10.40		MADE GROUND (brown mottled silty clay with bricks and chalk)
				J 777	2.20	35.30	
				J 778	10.60		Soft grey, green and brown mottled silty CLAY with shell fragments
				J 779	2.80	34.70	
				U 780	10.40		Firm grey/blue and green/brown mottled very sandy silty CLAY with occasional gravel
25/9			C 91	B 780	3.20	34.30	
25/9				J 781			Very dense brown fine to coarse SAND and fine to coarse subangular to subrounded GRAVEL
				B 782			
			C 73	J 783	13.00		
				B 784			
			C 77	J 785			
				J 786	6.20	31.30	Firm light brown/grey laminated clayey sandy SILT with occasional flints
				U 787	10.70		
			C129	B 788	6.90	30.60	Very dense fine to cobble subangular to subrounded GRAVEL and brown fine to coarse SAND
				J 789			
			C 57	B 790	12.10		
				J 791			
			C 8	B 792	9.00	28.50	Loose brown fine to coarse SAND with gravel and numerous fine to medium gravel sized chalk fragments
				J 793	11.00		
25/9		Low opt value probably due to adverse hydrostatic conditions			10.00	27.50	End of Borehole
Operator: IM		General Remarks: Pit dug to avoid services Piezometer installed to 9.0m Water added to assist drilling 3.20m to 7.00m					Appendix 1
Scale 10m/sheet							Sheet No. 54

SU 77 SW 310 [7290 7384]

Contract: Reading Cross Town Stage II						Borehole No. 14		
Client: Berkshire County Council						Sheet No. 1 of 1 Depth 0 to 10 metres.		
Equipment and Methods Light Cable Percussion Boring 150mm Diameter			Ground Level : (m.O.D.) 37.50		Job Number : S39/655			
			Coordinates :		Location :			
Orientation : Vertical					Dates : 27/9/89			
Daily Prog.	Water Levels	Remarks	In Situ Tests	Samples Taken	Depth (Thick)	Reduced Level	Description	Legend
				B-794	0.00	G.L.	Made Ground (Brown silty clay with traces of organic matter and zones of loose ash, chalk, brick, clinker and concrete)	
				U-795	(2.40)			
				J-796				
				U-797	2.40	35.10		
				J-798	(0.50)			
	27/9	Water level rose to 2.50m in 20 minutes	C 15	B-799 J-800	2.90	34.60	Soft to firm grey brown mottled silty CLAY with occasional fine gravel	
			C 54	B-801 J-802	(2.70)		Medium dense becoming dense coarse to fine SAND and coarse to fine subangular to subrounded GRAVEL	
			C 43	B-803 J-804				
				J-805	5.60	31.90	Firm white remoulded CHALK with lithorelics of weak chalk, becomes rubbly with depth. (Grade IV - V becomes grade IIII)	
				U-806				
				B-807				
			S 6	J-808				
				B-809				
				U-810	(4.40)			
			S 16					
					10.00	27.50	End of Borehole	

BGS Reference: SU77SW81
British National Grid:

Eastern L.S. Thames NRA

SU77SW 81 7294-7390

Kings Meadow Reading (Tesco site) Deep 268 SU 77/169 e SU77SW

3A

Owner	Licence No.	Nat. Grid Ref.	SU 7294 7390	
Occupier	IGS Ref. No.	Status		
Ground Level	m OD	ft. OD		
Level of Well Top	37.5 m OD	ft. OD	Aquifer <i>Chalk</i>	
Test Water Level	m bwt	ft. bwt	Summary of Geological Section	
Date	m OD	ft. OD	Thickness	Depth
Construction	18/06/80/28			
Depth bwt	Dis.	Linings (below well top)		
		From	To	Dis. Type
11.1		0	3.20 m	250 mm
		3.20 m	17.1 m	200 mm
Abstraction Rates				
Type of Pump				
gph	Chem./Bact. Anal.	YES	NO	
gpd	Well Driller			

Insufficient space has been allowed, continue in 'Notes' overleaf.

Site Plan

KINGS MEADOW, ELIZING, BEDFORDSHIRE.

BORING No: 3A
Continuation Bore No: 1

REPORT No: 4163/127/80

Depth (m)	S.P.T. (N)	Scale: 1mm = 10m	Log	Depth	Approx.	Description
11.00						Off white chalk with flints.
12.00						
13.00						
14.00						
15.00						
16.00						
17.00						

Upper Chalk

18/1/93

CLIENT: TESCO SUPERSTORES LIMITED
Cone Meter: Eyle Stewart Limited
Method of Boring: Cable Percussion

REPORT No: 4163/127/80
Boring Dated: 10/03/80
Boring Finished: 11/03/80

Water Sample	Rate of Inflow	Sealed off at	Sec. seal	10.05.80	11.05.80
1st: 3.30	Medium	Sec. seal		16.00	08.00
2nd: 3.30				7.50	7.50
3rd: 3.30				7.50	7.50
				4.50	3.20

Groundwater struck at 3.30m, 3.30m to 7.50m in twenty minutes. Water added to Special sealing and well casing installed at 17.50m.

Sample No.	Depth (m)	S.P.T. (N)	Scale: 1mm = 10m	Log	Depth	Description
639	1.00					Made Ground (black coarse sand with shunder web, clinker, brick fragments, pieces of wood fine, medium and coarse sub-angular gravel).
640	2.00					Green (medium) sand
641	3.00					Stiff brown and orange-brown sandy CLAY w/ rootlets.
642	4.00					Orange-brown very sandy fine medium and coarse sub-angular gravel with chalk and flint fragments.
643	5.00					
644	6.00					
645	7.00					
646	8.00					

Made Ground
Green sand
Clay
Gravel
(Quartz)

BGS Reference: SU77SW311
British National Grid:

SU 77 SW 311 [7295 7384]

Contract: Reading Cross Town Stage II				Borehole No. 15				
Client: Berkshire County Council				Sheet No. 1 of 2, in Borehole Depth 0 to 10 metres.				
Equipment and Methods Light Cable Percussion Boring 150mm Diameter		Ground Level : 37.40 m.O.D.		Job Number : 539/655				
Orientation : Vertical		Coordinates :		Location :				
				Dates : 28/9/89				
Daily Prog.	Water Levels	Remarks	In Situ Tests	Samples Taken	Depth (Thick)	Reduced Level	Description	Legend
				B 817	9.00	6.40	MADE GROUND (brown silty clay and grey silty clay with gravel, chalk and traces of brick)	
				U 818	12.00			
				J 819				
				J 820	2.00	35.40		
				U 821			Soft grey and brown mottled silty CLAY with traces of decaying organic matter	
				J 822	11.20			
				J 823				
	28/9	Water rose to 2.90m after 20 mins		W 825	3.20	34.20	Medium dense to dense brown coarse to fine SAND and coarse to fine subangular GRAVEL	
				W 841				
				W 842				
			C 20	W 827				
			C 44	W 829	13.80			
			C 14	B 831				
				J 832	7.00	30.40	Stiff to weak white rubbly becomes blocky CHALK with occasional flints	
				U 833				
				U 834				
			C 24	J 835				
				B 836				
			S 30	J 837	13.10			
28/9				B 838				
				U 839				
					10.00		Continued	
Operator IM		General Remarks:						Appendix 1
Scale 10m/sheet								Sheet No. 60

SU 77SW/311

Contract: Reading Cross Town Stage II				Borehole No. 15			
Client: Berkshire County Council				Sheet No. 2 of 2 Depth 10 to 20 metres.			
Equipment and Methods Light Cable Percussion Boring 150mm Diameter		Ground Level : 37.40 m.O.D. Coordinates :		Job Number : S39/655 Location : Dates : 28/9/89			
Orientation : Vertical							
Daily Prog.	Water Levels	Remarks	In Situ Tests	Samples Taken	Depth (Thick)	Reduced Level	Description
28/9				U 839 J 840	18.00 10.10	27.30	Stiff to weak white lobbly becomes blocky CHALK with occasional flints End of Borehole
General Remarks:			Appendix 1				
Operator IM			Sheet No. 61				
Scale 10m/sheet							

BGS Reference: SU77SW312
British National Grid:

SU 77 SW 312 [7300 7384]

Contract: Reading Cross Town Stage II				Borehole No. 16				
Client: Berkshire County Council				Sheet No. 1 of 2 Depth 0 to 10 metres				
Equipment and Methods Light Cable Percussion Boring 150mm Diameter		Ground Level : 36.00 m.O.D.		Job Number : S39/655				
Orientation : Vertical		Coordinates :		Location :				
Dates : 2/1/89								
Daily Prog.	Water Levels	Remarks	In Situ Tests	Samples Taken	Depth (Thick)	Reduced Level	Description	Legend
				B 843	0.00	36.00	MADE GROUND (brown silty sandy clay with gravel chalk fragments with ash and brick)	
				J 844	1.00	35.00	Soft grey sandy very silty CLAY with traces of fine gravel and chalk	
	3/10			U 845	1.30			
				J 846				
	2/10			J 847	2.30	33.70	Soft brown clayey SILT with pockets of fine gravel and sand, traces of decaying organic matter	
				U 848				
	2/10	Water rose to 2.60m after 20mins		U 849	1.20			
				M 875				
				M 876				
			C 13	B 850	3.50	32.50	Medium dense becoming dense brown coarse to fine sandy coarse to fine subangular GRAVEL	
				J 851				
			C 28	B 852				
				J 853	12.60			
			C 61	B 854				
				J 855				
				U 856	6.10	29.90	Stiff rubbly CHALK becomes blocky with depth, occasional flints, (Grade IV becomes III)	
				J 857				
				B 858				
			S 9	B 859				
				J 860				
				U 861	6.00			
				J 862				
				B 863				
	2/10		S 40	J 864				
				J 865				
					10.00		Continued	
Operator IM		General Remarks: Chiselling flint 12.01 to 12.60m (1 hour)						Appendix 1
Scale 10m/sheet								Sheet No 64

SU 77SW/312

Contract: Reading Cross Town Stage II				Borehole No. 16				
Client: Berkshire County Council				Sheet No. 1 of 2 Depth 10 to 20 metres.				
Equipment and Methods Light Cable Percussion Boring 150mm Diameter		Ground Level : 36.00 m.O.D. Coordinates :		Job Number : S39/655 Location : Dates : 2/1/89				
Orientation : Vertical								
Daily Prog.	Water Levels	Remarks	In Situ Tests	Samples Taken	Depth (Thick)	Reduced Level	Description	Legend
				U 866	10.00		Stiff rubbly CHALK becomes blocky with depth, occasional flints. (Grade IV becomes III)	
				J 867 8 868				
					16.00			
			S 44	J 869				
		Flints bend 12.10 to 12.60m		8 870	12.10	23.90	Weak white blocky CHALK with occasional flints. (Grade III)	
				U 871				
				J 872 8 873	12.90			
			S 53	J 874				
	2/10				15.00	21.00	End of Borehole	
Operator IM		General Remarks: Chiselling flint 12.01 to 12.60m (1 hour)						Appendix 1
Scale 10m/sheet								Sheet No. 65

BGS Reference: SU77SW313
British National Grid:

SU 77 SW 313 [7301 7384]

Contract: Reading Cross Town Stage II				Borehole No. 17				
Client: Berkshire County Council				Sheet No. 1 of 2 of Borehole Depth 0 to 10 metres.				
Equipment and Methods Light Cable Percussion Boring 150mm Diameter			Ground Level : 35.90 m.O.D.		Job Number : S39/655			
Orientation : Vertical			Coordinates :		Location :			
					Dates : 24/10/89 27/10/89			
Daily Prog.	Water Levels	Remarks	In Situ Tests	Samples Taken	Depth (Thick)	Reduced Level	Description	Legend
				B-1035	0.00	G.L.	MADE GROUND (brown silty sandy clay with gravel and bricks)	
				J-1036	0.50	35.40	Firm brown friable silty CLAY with traces of fine gravel and shells	
				J-1037	1.10	34.80	Soft grey sandy very silty CLAY with fragments of decaying wood and plant remains and occasional pockets of silt and sand. becomes peaty with depth	
				U-1038				
				U-1039				
						(2.20)		
				J-1040				
				U-1061				
				W-1062				
				W-1063	3.30	32.60	Medium dense becoming dense brown coarse to fine SAND and coarse to fine subangular GRAVEL	
			C 12	J-1043				
			C 20	J-1044	12.50			
				J-1045				
			C 35	B-1046				
				J-1047				
					5.80	30.10	Stiff becoming weak white rubbly to blocky CHALK with occasional flints (Grade IV becomes grade III)	
				U-1048				
				U-1049				
				B-1050				
			S 29	J-1051				
				B-1052	(4.20)			
				U-1053				
				J-1054				
				B-1055				
			S 44	J-1056				
					10.00	25.90	Continued	
Operator NF			General Remarks: Chiselling flint bend 8.0 to 8.3m (1/2 hour)					Appendix 1
Scale 10m/sheet								Sheet No. 68

SU 77 SW / 313

Contract: Reading Cross Town Stage II				Borehole No. 17			
Client: Berkshire County Council				Sheet No. 2 of 2 Depth 10 to 20 metres.			
Equipment and Methods Light Cable Percussion Boring 150mm Diameter		Ground Level : 35.90 m.O.D. Coordinates :		Job Number : S39/655 Location : Dates : 24/10/89 27/10/89			
Orientation : Vertical							
Daily Prog.	Water Levels	Remarks	In Situ Tests	Samples Taken	Depth (Thick)	Reduced Level	Description
				B 1057	10.00	25.90	Weak to moderately weak white blocky CHALK joints from 60 to >100mm apart frequent flints (Grade III to II)
				U 1058			
				J 1059			
				B 1060			
			S 55	J 1061			
				B 1079			
				B 1064			
				U 1065			
				J 1066			
				J 1067			
			S 55	J 1068			
				B 1069			
				U 1070			
				J 1071	10.00		
				J 1072			
			S 53	J 1073			
				B 1074			
				U 1075			
				J 1076			
				J 1077			
			S107	J 1078			
				U 1080			
				J 1081			
				B 1082			
			S134	J 1083			
					20.00	15.90	End of Borehole
Operator NF		General Remarks: Chiselling flint bend 8.0 to 8.3m (1/2 hour)					
Scale 10m/sheet		Appendix 1 Sheet No. 69					

BGS Reference: SU77SW314
British National Grid:

SU 77 SW 314 [7303 7386]

Contract: Reading Cross Town Stage II				Borehole No. 18				
Client: Berkshire County Council				Sheet No. 1 of 2 Depth 0 to 10 metres				
Equipment and Methods Light Cable Percussion Boring 200mm		Ground Level : 37.50 m.O.D. Coordinates :		Job Number : S39/655 Location : Dates : 24/10/89 27/10/89				
Orientation : Vertical								
Daily Prog.	Water Levels	Remarks	In Situ Tests	Samples Taken	Depth (Thick)	Reduced Level	Description	Legend
				U	0.00		MADE GROUND (dark brown silty clay with ash, flints, clinker and bricks)	
				J 244	0.85			
				J 245	0.85	36.65	MADE GROUND (light brown silty clay with bricks, flints and chalk)	
	24/10			J 246	1.50	36.00		
	25/10			J 247	1.10		MADE GROUND (dark brown silty clay with wood, shells, ash clinker and bricks)	
	27/10		S 10	J 248	2.60	34.90		
				J 249	2.60			
				W 254	0.80		Loose to medium dense dark grey very clayey silty fine SAND with decaying vegetation and shell fragments	
				U 250	3.40	34.10		
	24/10	Water level rose to 2.80m after 20 minutes		J 251	0.85		Soft to firm dark brown silty CLAY with shells and black organic material	
	25/10			U 252	4.25	33.25		
			C 13	W 254	1.25		Medium dense brown fine to coarse SAND and fine to coarse subangular GRAVEL	
				B 253	5.50	32.00		
	25/10			J 255	1.50		Medium dense brown fine to coarse SAND and fine to coarse subangular GRAVEL with hard chalk nodules	
			C 15	B 256	7.00	30.50		
	24/10			J 257	17.00		Stiff to weak to off white rubbly to blocky CHALK with orange staining and orange speckling. (Grade IV to III)	
	24/10		S 10	B 258				
				J 259				
		Flint sand		U 260				
				J 261				
			S 12	B 262				
				J 263				
					10.00			
							Continued	
Operator NF		General Remarks: Permeability test made at 15.0m Piezometer installed at 7.0m					Appendix 1	
Scale 10m/sheet							Sheet No. 72	

SU 77SW/314

Contract: Reading Cross Town Stage II				Borehole No. 18				
Client: Berkshire County Council				Sheet No. 10 of 20 Depth 10 to 20 metres.				
Equipment and Methods Light Cable Percussion Boring 200mm		Ground Level : 37.50 m.O.D. Coordinates :		Job Number : S39/655 Location : Dates : 24/10/89 27/10/89				
Orientation : Vertical								
Daily Prog.	Water Levels	Remarks	In Situ Tests	Samples Taken	Depth (Thick)	Reduced Level	Description	Legend
				U 264	16.00		Stiff to weak to off white rubbly to blocky CHALK with orange staining and orange speckling. (Grade IV to III)	
				J 265				
			S 27	B 266				
				J 267				
				U 268	17.00			
				J 269				
			S 35	B 270				
				J 271				
25/10				U 272	14.00	23.50		
25/10		Flint band		J 273			Weak to moderately weak white blocky CHALK occasional flints (Grade III to II)	
			S126 /295	B 274				
				J 275				
26/10				U 276				
26/10				J 277				
27/10			S135	B 278	16.00			
				J 279				
				U 280				
				J 281				
			S132	B 282	20.00	17.50	End of Borehole	
Operator NF		General Remarks: Permeability test made at 15.0m Piezometer installed at 7.0m						Appendix 1
Scale 10m/sheet								Sheet No 73

BGS Reference: SU77SW315
British National Grid:

SU 77 SW 315 [7305 7389]

Contract: Reading Cross Town Stage II				Borehole No. 19				
Client: Berkshire County Council				Sheet No. 1 of 1 Depth 0 to 10 metres				
Equipment and Methods Light Cable Percussion Boring 150mm Diameter		Ground Level : 35.75 M.O.D.		Job Number : S39/655				
Orientation : Vertical		Coordinates :		Location :				
				Dates : 4/10/89 5/10/89				
Daily Prog.	Water Levels	Remarks	In Situ Tests	Samples Taken	Depth (Thick)	Reduced Level	Description	Legend
				B 1011	0.00	35.75	Brown silty CLAY with occasional gravel and shells	1011
				J 1012	0.80	34.95	Soft to firm grey silty CLAY with traces of decaying organic matter	1012
				M 1033 M 1034 U 1013	1.70	34.05	Soft black grey very silty CLAY with occasional fine gravel, traces of decaying organic material and shells	1033 1034 1013
				J 1014 J 1015 U 1016	3.00	32.75	Medium dense to dense brown coarse to fine sandy coarse to fine subangular GRAVEL	1014 1015 1016
				C 16 B 1017 J 1018	4.70	31.05		1017 1018
				C 49 B 1019 J 1020	6.70	29.05		1019 1020
		Some remoulded chalk from 5.30m		C 10 B 1021 J 1022	8.70	27.05	Stiff becoming weak white rubbly CHALK some orange staining along block surfaces and zones of remoulded chalk occasional flints	1021 1022
				U 1023 U 1024 J 1025 B 1026	10.00	25.75	Weak white blocky CHALK occasional flints (Grade III)	1023 1024 1025 1026
		Flint band 7.80 to 8.30m		S 25 J 1027				1027
				B 1028 U 1029 J 1030 B 1031				1028 1029 1030 1031
				S 37 J 1032				1032
					10.00	25.75	End of Borehole	
Operator IM		General Remarks: Chiselling flints 7.8 to 8.30m (1 hour) Pit dug to avoid services					Appendix 1	
Scale 10m/sheet							Sheet No. 77	

SU77SW 316 [7305 7384]

[illegible]

Sheet No. 81

54 77 SW / 316

Contract: Reading Cross Town Stage II				Borehole No. 20				
Client: Berkshire County Council				Sheet No. 3 of 3 Depth 20 to 30 metres.				
Equipment and Methods Light Cable Percussion Boring 150mm Diameter			Ground Level : 35.70 m.O.D. Coordinates :		Job Number : 539/655 Location : Dates : 12/12/89 17/10/89			
Orientation : Vertical								
Daily Prog.	Water Levels	Remarks	In Situ Tests	Samples Taken	Depth (Thick)	Reduced Level	Description	Legend
				B 1135	20.00		Weak to moderately weak white blocky CHALK with flints. Frequent large flints below 15.50m (Grade III becomes grade III)	
			S109	J 1136				
				B 1137				
				U 1138				
				B 1139				
			S 76	J 1140	14.00			
				B 1141				
				U 1142				
				U 1143				
				J 1144	25.00	10.70		End of Borehole
Operator IM			General Remarks: Piezometer installed to 6.0m Pit dug to avoid services Permeability test made at 4.52m Chiselling flints 11.50m to 15.00m					Appendix 1
Scale 10m/sheet								Sheet No 82

BGS Reference: SU77SW317
British National Grid:

SU 77 SW 317 [7309 7383]

Contract: Reading Cross Town Stage II				Borehole No. 21				
Client: Berkshire County Council				Sheet No. 1 of 3 Depth 0 to 10 metres.				
Equipment and Methods Light Cable Percussion Boring 150mm Diameter		Ground Level : 36.25 m.O.D.		Job Number : S39/655				
Orientation : Vertical		Coordinates :		Location :				
				Dates : 26/9/89 27/9/89				
Daily Prog.	Water Levels	Remarks	In Situ Tests	Samples Taken	Depth (Thick)	Reduced Level	Description	Legend
					0.00	36.25	MADE GROUND (brick, rubble and silty sand)	
				B 885	0.40	35.85	Soft to firm brown silty CLAY with traces of decaying organic matter	
				J 886	1.20			
				U 887	1.60	34.65	Soft to firm brown mottled grey silty CLAY with traces of decaying organic matter	
				J 888	1.90			
				J 889	2.50	33.75	Soft orange and grey mottled brown silty sandy CLAY	
				U 890	2.90	33.35	Soft to very soft orange white sandy SILT	
	26/9 27/9	Water level rose to 1.7m in 20 minutes		J 891	3.50	32.75	Medium dense becoming dense coarse to fine SAND and coarse to fine subangular GRAVEL	
			C 13	B 893 W 894 W 895				
	26/9		C 71 / 150	J 896 B 897	12.60			
			C 41	B 899	6.10	30.15	Soft remoulded CHALK with harder chalk nodules and abundant flint GRAVEL	
				B 899 J 900 U 901 J 901	6.80	29.45	Stiff white remoulded CHALK with occasional lithorelics of hard chalk frequents flints (Grade V to IV)	
			S 36	J 902 B 903	11.70			
					8.50	27.75	Stiff to weak white rubbly to blocky CHALK with frequent flints (Grade IV)	
			S 22	J 904 B 905	12.50			
					10.00			
Continued								
Operator RM		General Remarks: Pit dug to avoid services Piezometer installed to 5.50m Chiselling flints various levels (4hours)						Appendix 1
Scale 10m/sheet								Sheet No 86

SU77SW 317 [7309 7383]

Contract: Reading Cross Town Stage II				Borehole No. 21			
Client: Berkshire County Council				Sheet No. 2 of 3 Depth 10 to 20 metres.			
Equipment and Methods Light Cable Percussion Boring 150mm Diameter		Ground Level : 36.25 m.O.D. Coordinates :		Job Number : S39/555 Location : Dates : 26/9/89 27/9/89			
Orientation : Vertical							
Daily Prog.	Water Levels	Remarks	In Situ Tests	Samples Taken	Depth (Thick)	Reduced Level	Description
26/9				U 906	10.90		Stiff to weak white rubble to blocky CHALK with frequent flints (Grade IV)
26/9				J 907	(2.50)		
				J 908	11.00	25.25	Stiff becoming moderately weak white blocky CHALK with frequent flints occasionally cobble size (Grade IV to III possible Grade II below 15m)
27/9				U 909			
				J 910			
				J 911			
			S 72	J 912			
				B 913			
				U 914			
				J 915			
				J 916			
			S 53 /150	J 917		(9.30)	
				B 918			
				U 919			
				J 920			
				J 921			
				B 922			
			S 65 /150	J 923			
				B 924			
				UL			
					20.00		Continued
Operator RM		General Remarks: Pit dug to avoid services Piezometer installed to 5.50m Chiselling flints various levels (4hours)				Appendix 1	
Scale 10m/sheet						Sheet No. 87	

SU77SW/317

Contract: Reading Cross Town Stage II				Borehole No. 21				
Client: Berkshire County Council				Sheet No. 3 of 3 Depth 20 to 30 metres.				
Equipment and Methods Light Cable Percussion Boring 150mm Diameter				Ground Level : 36.25 m.O.D.		Job Number : 539/655		
Orientation : Vertical				Coordinates :		Location :		
						Dates : 26/9/89 27/9/89		
Daily Prog.	Water Levels	Remarks	In Situ Tests	Samples Taken	Depth (Thick)	Reduced Level	Description	Legend
27/9			S 65 /150	J 925	20.00		Stiff becoming moderately weak white blocky CHALK with frequent flints occasionally cobble size (Grade IV to VII possible Grade II below 15m) -- End of Borehole	
			S 35 /150		20.30	15.95		
Operator RM			General Remarks: Pit dug to avoid services Piezometer installed to 5.50m Chiselling flints various levels (4hours)					Appendix 1
Scale 10m/sheet								Sheet No. 88

BGS Reference: SU77SW318
British National Grid:
3.4

SU 77 SW 318 [7311 7386]

Contract: Reading Cross Town Stage II				Borehole No. 22				
Client: Berkshire County Council				Sheet No. 1 of 2 Depth 0 to 10 metres.				
Equipment and Methods Light Cable Percussion Boring 150mm Diameter		Ground Level : 36.10 m.O.D.		Job Number : S39/655				
Orientation : Vertical		Coordinates :		Location :				
				Dates : 2/10/89 3/10/89				
Daily Prog.	Water Levels	Remarks	In Situ Tests	Samples Taken	Depth (Thick)	Reduced Level	Description	Legend
					0.00		MADE GROUND (fill rubble gravels to 0.2 from 0.2 old wall foundations blockwork on a concrete base from 0.5 soft to firm brown clay)	
				B-972	(1.40)			
				B-973				
				U-974	1.40	34.70		
				J-975	(1.60)		Soft grey orange and brown mottled silty CLAY becomes dark greenish grey with depth, traces of decaying organic matter and shells	
				U-976				
	2/10	Water level rose to 1.80m		J-977	3.00	33.10		
	3/10			B-978	3.40	32.70	Soft dark brown amorphous PEAT with occasional gravel	
	2/10		C 19	B-979			Medium dense becoming dense brown coarse to fine SAND and coarse to fine subangular GRAVEL occasional cobbles	
				B-980				
			C 47	J-981	(2.40)			
				B-982				
				J-983				
			C 37	B-984	5.80	30.30	Medium dense to dense coarse to fine subangular GRAVEL and cobbles in a matrix of soft remoulded chalk	
				B-985	6.40	29.70	Stiff to weak white rubbly to blocky CHALK flints often orange stained occasional flints	
			C 22	B-986				
				U-987	(1.60)			
	2/10			B-988	8.00	28.10	Weak to moderately weak white blocky CHALK with frequent flints	
	2/10							
			S 32	J-989	(5.70)			
				B-990				
					10.00		Continued	
Operator RM		General Remarks: Pit dug to avoid services Chiselling cobbles 5.80m to 6.40m (1 1/2 hours) Chiselling flints 13.7m to 13.9m (1 hour) Piezometer installed to 6.00m						Appendix 1
Scale 10m/sheet								Sheet No. 92

SU77SW/318

Contract: Reading Cross Town Stage II				Borehole No. 22			
Client: Berkshire County Council				Sheet No. 2 of 2 Depth 10 to 20 metres			
Equipment and Methods Light Cable Percussion Boring 150mm Diameter		Ground Level : 36.10 m.O.D. Coordinates :		Job Number : S39/655 Location : Dates : 2/10/89 3/10/89			
Orientation : Vertical							
Daily Prog.	Water Levels	Remarks	In Situ Tests	Samples Taken	Depth (Thick)	Reduced Level	Description
					10.00		Weak to moderately weak white blocky CHALK with frequent flints
				U 991			
				J 992			
				U 993			
3/10			S 34	J 994 B 995	(5.70)		
				B 995			
				U 997 B 998			
3/10			C 69		13.70 13.80	22.40 22.20	Large FLINT obstruction End of Borehole
Operator RM			General Remarks: Pit dug to avoid services Chiselling cobbles 5.80m to 6.40m (1 1/2 hours) Chiselling flints 13.7m to 13.9m (1 hour) Piezometer installed to 6.00m				Appendix 1
Scale 10m/sheet							Sheet No. 93

BGS Reference: SU77SW319
British National Grid:

SU 77 SW 319 [7311 7384]

Contract: Reading Cross Town Stage II				Borehole No. 23				
Client: Berkshire County Council				Sheet No. 1 of 3 Depth 0 to 10 metres				
Equipment and Methods Light Cable Percussion Boring 150mm Diameter		Ground Level : 36.30 m.O.D.		Job Number : S39/655				
Orientation : Vertical		Coordinates :		Location :				
				Dates : 28/9/89 29/9/89				
Daily Prog.	Water Levels	Remarks	In Situ Tests	Samples Taken	Depth (thick)	Reduced Level	Description	Legend
					0.00	G.L.		
				B 926	0.30	36.00	MADE GROUND (brown silty sandy clay ash and brick)	
				J 927	1.20		MADE GROUND (brown silty sandy clay with ash, bricks and gravel)	
				U 928	1.50	34.80		
				J 929	10.60		Soft grey and brown mottled silty CLAY	
	28/9	Seepage		U 930	2.30	34.00		
				J 931	11.30		Soft grey and brown mottled silty CLAY with occasional shells and traces of decaying organic matter	
				J 932				
	29/9			U 933	3.60	32.70		
	28/9	Waterlevel rose to 1.90m in 20 minutes		J 934			Medium dense to dense brown coarse to fine SAND and coarse to fine subangular GRAVEL	
			S 21	J 935				
				B 936				
				B 937				
				J 938				
				B 939	12.20			
			C 41	J 940				
				B 941				
				J 942				
				B 943				
				B 944	5.80	30.50		
			S 32	J 945	10.40		Coarse to fine GRAVEL in a matrix of remoulded chalk	
				B 946	6.20	30.10		
							Stiff white rubly to blocky CHALK with orange staining on joints frequent flints (Grade IV to III)	
	28/9			U 947				
				J 948	14.50			
				U 949				
				J 950				
					10.00			
							Continued	
Operator RM		General Remarks: Pit dug to avoid services Chiselling flints 10m to 24m various levels (1 1/2 hours) Chiselling flint at 24.3m (1 hour)					Appendix 1	
Scale 10m/sheet							Sheet No. 97	

5477SW/319

Contract: Reading Cross Town Stage II				Borehole No. 23			
Client: Berkshire County Council				Sheet No. 2 of 3 Depth 10 to 20 metres.			
Equipment and Methods Light Cable Percussion Boring 150mm Diameter		Ground Level : 36.30 m.O.D. Coordinates :		Job Number : S39/655 Location : Dates : 28/9/89 29/9/89			
Orientation : Vertical							
Daily Prog.	Water Levels	Remarks	In Situ Tests	Samples Taken	Depth (Thick)	Reduced Level	Description
28/9			S 37	J 951 B 952	10.00 (4.30) 10.50	25.80	Stiff white rubly to blocky CHALK with orange staining on joints frequent flints (Grade IV to III)
28/9							Weak to moderately weak white blocky CHALK frequent flints (Grade III becomes grade II)
29/9				U 953 J 954			
			S 43	J 955 B 956			
				U 957 J 958		113.80	
				J 959			
			S 67 /225	J 960 B 961			
				U 962 J 963			
			S 62 /150	J 964 B 965		20.00	
Continued							
Operator RM		General Remarks: Pit dug to avoid services Chiselling flints 10m to 24m various levels (1 1/2 hours) Chiselling flint at 24.3m (1 hour)					Appendix 1
Scale 10m/sheet							Sheet No.98

Contract: Reading Cross Town Stage II						Borehole No. 23	
Client: Berkshire County Council						Sheet No. 3 of 3 Depth 20 to 30 metres.	
Equipment and Methods Light Cable Percussion Boring 150mm Diameter			Ground Level : 36.30 m.O.D.			Job Number : S39/655	
Orientation : Vertical			Coordinates :			Location :	
						Dates : 28/9/89 29/9/89	
Daily Prog.	Water Levels	Remarks	In Situ Tests	Samples Taken	Depth (Thick)	Reduced Level	Description
					20.00		Weak to moderately weak white blocky CHALK frequent flints (Grade III becomes grade III)
				U 966 B 967			
					13.80		
			S 78 /225	J 968 B 969			
			S 61 /150	J 970 B 971			
29/9					24.30	12.00	End of Borehole
General Remarks: Pit dug to avoid services Chiselling flints 10m to 24m various levels (1 1/2 hours) Chiselling flint at 24.3m (1 hour)							
Operator RM							
Scale 10m/sheet							
Appendix 1							
Sheet No 99							

BGS Reference: SU77SW320
British National Grid:

SU 77 SW 320 [7313 7384]

Contract: Reading Cross Town Stage II				Borehole No. 24				
Client: Berkshire County Council				Sheet No. 1 of 2 Depth 0 to 10 metres				
Equipment and Methods Light Cable Percussion Boring 150mm Diameter		Ground Level : (m.O.D.) 36.50		Job Number : 539/655		Location :		
Orientation : Vertical		Coordinates :		Dates : 5/10/89 10/10/89				
Daily Prog.	Water Levels	Remarks	In Situ Tests	Samples Taken	Depth (mick)	Reduced Level	Description	Legend
					0.00	G.L.		
					(0.40)		TOPSOIL (fill material)	
				B 218	0.40	36.10	MADE GROUND (firm brown clay)	
				J 219	(1.10)			
5/10				U 220	1.50	35.00	Soft grey and brown mottled silty CLAY with traces of decaying organic material	
	7 9/10			J 221	(1.30)			
				U 222	2.80	33.70	Soft grey/orange silty sandy CLAY with abundant fine chalk particles	
	9 9/10			J 223	(0.50)			
				J 224	3.40	33.10	Medium dense to dense brown coarse to fine SAND and coarse to fine subangular GRAVEL. traces of chalk below 5.00m	
	5/10	Standing at 1.90m after 20 mins	C 15	B 225				
	5/10			J 226				
			C 29	B 227	(2.90)			
				B 228				
			C 67	B 229				
				B 230				
				B 231				
				U 232	6.30	30.20	Stiff white rubblely to blocky CHALK with some remoulded chalk and occasional flints (grade IV)	
				J 233				
			S 30	J 234	(2.70)			
				B 235				
				U 236				
				J 237				
6/10			S 37	J 238	9.00	27.50	Weak white blocky CHALK occasional manganese staining along joints occasional flints (grade IV to III)	
				B 239				
				B 398	(6.50)			
5/10				J 399	10.00			
							Continued	
Operator RM		General Remarks:						Appendix 1
Scale 10m/sheet								Sheet No 102

[illegible]

BGS Reference: SU77SW622
British National Grid:

Date		10th September 1986		SUTTSW 622		D 0.60 x 1.50m		Bearing → 052°	
Level		36.75m.O.D.		7314 73853					

GL	A	B	C	D	GL
		(1)			
		(2)			
10					10
		(3)			
20					20
		(4)			
30					30
40					40
	End of Trial Pit				

Samples		Strata		Test Depth m.	Cu kNm ²	Remarks
Depth	Type	No.	Description			
0.20	D	1	MADE GROUND: Light brown fine sandy silty clay.			
		2	MADE GROUND: Dark brown slightly clayey fine to coarse sand with rope, glass, wood, iron, wire, plastic, brick and bottles.			
1.50	BD	3	Very soft light grey brown slightly sandy silty CLAY with orange brown staining and carbonaceous inclusions. (Alluvium)			
		4	Light brown very coarse sandy fine to medium sub-rounded GRAVEL. (Valley Gravel)			

Plant	JCB 3CY	Water	1.00m stroke - very rusty muddy water 3.50m Extremely fast ingress 0.5m/1 minute	Cu - Approximate value of undrained shear strength from hand vane
Shored to		Stability	Instability in gravels	

Trial Pit Record exploration associates	Project	Contract	E6043
	A329(M) Broken Brow and North Earley Link Royal County of Berkshire	Trial Pit	15

SU 77 SW 321 [7316 7385]

Contract: Reading Cross Town Stage II						Borehole No. 25		
Client: Berkshire County Council						Sheet No. 10 of 12		
Equipment and Methods Light Cable Percussion Boring 150mm Diameter			Ground Level : 35.00 m.O.D.			Job Number : S39/655		
			Coordinates :			Location :		
Orientation : Vertical						Dates : 10/10/89 12/10/89		
Daily Prog.	Water Levels	Remarks	In Situ Tests	Samples Taken	Depth (Thick)	Reduced Level	Description	Legend
					-0.00	35.00	MADE GROUND (firm brown silty sandy clay with gravel ash brick and chalk fragments)	
				H 1				
				U 2	(1.70)			
	V 10/10 C 10/10	Waterlevel rose to 1.59m in 20 minutes		J 3 J 4 J 5 J 6 J 7 J 8 J 9 J 10 J 11 J 12	1.70	34.30	Soft greenish grey silty CLAY with traces of decaying organic matter occasional pockets of grey sandy silt below 2.4m	
	V 12/10 V 11/10			B 14 J 15	(1.55)			
10/10 10/10			C 48	J 16 J 17	(3.25)	32.75	Dense brown coarse to fine SAND and coarse to fine subangular GRAVEL occasional cobbles	
			C 51	B 18 J 19	(3.25)			
		Cobbles become more frequent below 5.0m	C 31	J 20 U 21	6.50	29.50	Stiff white rubblely to blocky CHALK with orange staining on block surfaces (Grade VI)	
				J 22 J 23 J 24 J 25 J 26 J 27 J 28	(3.50)			
11/10 12/10			S 68	J 29 B 30 J 31	10.00	25.00		
							Continued	
Operator JC		General Remarks: Permeability test made at 9.0m						Appendix 1
Scale 10m/sheet								Sheet No.10 of 12

5477SW/321

Contract: Reading Cross Town Stage II				Borehole No. 25				
Client: Berkshire County Council				Sheet No. 2 of 2 Depth 10 to 20 metres.				
Equipment and Methods Light Cable Percussion Boring 150mm Diameter		Ground Level : 36.00 m.O.D.		Job Number : 539/655				
Orientation : Vertical		Coordinates :		Location :				
				Dates : 10/10/89 12/10/89				
Daily Prog.	Water Levels	Remarks	In Situ Tests	Samples Taken	Depth (Thick)	Reduced Level	Description	Legend
				U 32	18.00	26.00	Weak white blocky CHALK with occasional orange staining on joint surfaces occasional flints (Grade IV to III)	
				J 33				
				J 34				
				B 35				
			S 70	J 36				
11/10				J 37				
				U 38				
				J 39				
				J 40	(5.50)			
			S 68	J 41				
				J 42				
				J 43				
				U 44				
				J 45				
				J 46				
				J 47				
			S 82 / 150	J 48				
12/10					15.50	20.50	End of Borehole	
Operator JC		General Remarks: Permeability test made at 9.0m						Appendix 1
Scale 10m/sheet								Sheet No. 107

BGS Reference: SU77SW604
British National Grid:

Logging		Properties			Strata		SUTTSW 604				
Type	Cu kPa	W%	SPT N	Description	73175	73854	Depth	Level	Legend		
				TOPSOIL			6.L.	36.28			
D/W				Loose light brown mottled grayish brown very clayey slightly sandy SILT with organic inclusions fine chalk fragments and thin beds of coarse sand and fine gravel			0.40	35.88			
D											
CB	46		2								
1.95											
D											
2.95											
CB			2								
3.45											
M(5)	(B)	89		Soft black clayey PEAT			2.80	33.48			
6.0											
D							3.60	32.68			
4.45		11	22	Medium dense light brown white and grey very sandy fine medium and coarse rounded flint and chalk GRAVEL							
4.70											
5.45			21								
CB											
5.70											
D											
6.45		10	22								
CB											
6.80			22				6.70	29.58			
7.45			23	Rubby white mottled light yellowish brown CHALK with silty chalk matrix and flints (Grade III)							
CB											
7.70		28									
D											
8.45			27								
CB											
8.70											
D											
9.45			33								
CB											
10.00											
D				Continued over from 10.00m							
Drilling					Ground Water						
Type	From	To	Size	Fluid	Struck	Behaviour	Sealed	Date	Hole	Cased	Water
Shell and Auger	G.L.	20.05	0.15	-	3.60	Rose to 0.3m in 15 minutes	7.00	10.9.86	10.00	10.00	9.30
								11.9.86	10.00	10.00	8.70
								11.9.86	20.05	18.00	15.90
Remarks											
Inspection Pit dug to 1.0m											
Piezometer installed; Tip at 6.3m; sand filter 5.5m - 6.5m											
Borehole Record					Project				Contract		
exploration associates					A329(M) Broken Brow and North Earley Link Royal County of Berkshire				E6043		
									Borehole 13 Sheet 1 of 2		

Sampling		Properties			Strata		SU77SW 604					
	Type	Cu kPa	W%	SPT N	Description	Depth	Level	Legend				
9.00-10.95	CB		29	32	Continued from 10.00m Rubby white occasionally mottled yellowish brown CHALK with some silty matrix and flints (Grade III)							
10.50	D		24									
11.00-12.45	CB			30								
13.00	D											
13.50-13.95	CB			31								
14.50	D		29									
15.00-15.45	CB			30								
16.00	D											
16.50-16.95	CB			29								
17.50	D		29									
18.00-18.45	CB			46	Becoming Grade II							
19.30	D		31									
19.60-20.05	CB			49								
					End of Borehole	20.00	16.28					
Drilling					Ground Water							
Type	From	To	Size	Fluid	Struck	Behaviour	Sealed	Date	Hole	Cased	Water	
Remarks												
Borehole Record					Project			Contract E6043				
exploration associates					A329(M) Broken Brow and North Earley Link Royal County of Berkshire			Borehole 13 Sheet 2 of 2				

SU 77 SW 322 [7320 7386]

Contract: Reading Cross Town Stage II				Borehole No. 26				
Client: Berkshire County Council				Sheet No. 1 of 1 Depth 0 to 10 metres				
Equipment and Methods Light Cable Percussion Boring 150mm Diameter			Ground Level : 35.75 m.O.O.		Job Number : S39/655			
Orientation : Vertical			Coordinates :		Location :			
					Dates : 3/10/89 4/10/89			
Daily Prog.	Water Levels	Remarks	In Situ Tests	Samples Taken	Depth (Thick)	Reduced Level	Description	Legend
					0.00	35.75	MADE GROUND (brown silty sandy clay with brick ash and gravel)	
				B 999	0.30	35.45	Soft brown and grey mottled silty CLAY	
				J 1000 U 1001	1.40	34.35	Very soft grey silty CLAY	
				J 1002 J 1003	1.70	34.05	Soft brown and black amorphous clayey PEAT interbedded with soft grey silty CLAY	
				U 1004 J 1005	(2.10)			
				U 1007				
				J 1008 B 1009	3.80	31.95	Coarse to fine sandy GRAVEL in a matrix of soft silty CLAY	
				B 1010	4.80	31.75	Medium Dense brown coarse to fine SAND and coarse to fine subangular GRAVEL	
				B 1011	4.60	31.15	Sandy gravel in a matrix of soft remoulded CHALK	
				U 1012 J 1013	4.80	30.85	Stiff becoming weak white rubbly becoming blocky CHALK with frequent flints. Some orange staining on flint surfaces at upper levels (Grade IV becomes III)	
				J 1014 B 1015	(5.10)			
				U 1016 J 1017				
				U 1018 J 1019				
				U 1020 J 1021				
				U 1022 J 1023				
				U 1024 J 1025				
				U 1026 J 1027				
				U 1028 J 1029				
				U 1030 J 1031				
				U 1032 J 1033				
				U 1034 J 1035				
				U 1036 J 1037				
				U 1038 J 1039				
				U 1040 J 1041				
				U 1042 J 1043				
				U 1044 J 1045				
				U 1046 J 1047				
				U 1048 J 1049				
				U 1050 J 1051				
				U 1052 J 1053				
				U 1054 J 1055				
				U 1056 J 1057				
				U 1058 J 1059				
				U 1060 J 1061				
				U 1062 J 1063				
				U 1064 J 1065				
				U 1066 J 1067				
				U 1068 J 1069				
				U 1070 J 1071				
				U 1072 J 1073				
				U 1074 J 1075				
				U 1076 J 1077				
				U 1078 J 1079				
				U 1080 J 1081				
				U 1082 J 1083				
				U 1084 J 1085				
				U 1086 J 1087				
				U 1088 J 1089				
				U 1090 J 1091				
				U 1092 J 1093				
				U 1094 J 1095				
				U 1096 J 1097				
				U 1098 J 1099				

BGS Reference: SU77SW323
British National Grid:

SU77 SW 323 [7320 7385]

Contract: Reading Cross Town Stage II				Borehole No. 27			
Client: Berkshire County Council				Sheet No. 27 of 27 Depth 0 to 10 metres			
Equipment and Methods Light Cable Percussion Boring 150mm Diameter		Ground Level : 36.60 m.O.D. Coordinates :		Job Number : S39/555 Location :		Dates : 4/10/89 5/10/89	
Orientation : Vertical							
Daily Prog.	Water Levels	Remarks	In Situ Tests	Samples Taken	Depth (Thick)	Reduced Level	Description
					0.00	G.L.	MADE GROUND (soft brown silty clay ash gravel brick occasional chalk. Becomes clay with traces of ash and brick)
				B 197			
				J 198	1.70		
				U 199		34.90	
				J 200	1.70		
				U 201			
				J 202	2.80	33.80	Very soft greenish grey silty CLAY with traces of decaying organic matter
				U 203			
				J 204	10.90		Very soft to soft brown and black amorphous clayey PEAT interbedded with silty clay
				U 205		32.90	
				B 206	3.70		
				J 207			Medium dense brown coarse to fine SAND and cobbles, coarse to fine subangular GRAVEL occasional traces of chalk
				U 208	5.40	31.20	
				J 209			Stiff becoming weak white rubblely to blocky CHALK with frequent flints (Grade IV becomes III)
				U 210			
				J 211			
				U 212			
				J 213	4.60		
				U 214			
				J 215			
				U 216			
				J 217			
				U 218			
				J 219			
				U 220			
				J 221			
				U 222			
				J 223			
				U 224			
				J 225			
				U 226			
				J 227			
				U 228			
				J 229			
				U 230			
				J 231			
				U 232			
				J 233			
				U 234			
				J 235			
				U 236			
				J 237			
				U 238			
				J 239			
				U 240			
				J 241			
				U 242			
				J 243			
				U 244			
				J 245			
				U 246			
				J 247			
				U 248			
				J 249			
				U 250			
				J 251			
				U 252			
				J 253			
				U 254			
				J 255			
				U 256			
				J 257			
				U 258			
				J 259			
				U 260			
				J 261			
				U 262			
				J 263			
				U 264			
				J 265			
				U 266			
				J 267			
				U 268			
				J 269			
				U 270			
				J 271			
				U 272			
				J 273			
				U 274			
				J 275			
				U 276			
				J 277			
				U 278			
				J 279			
				U 280			
				J 281			
				U 282			
				J 283			
				U 284			
				J 285			
				U 286			
				J 287			
				U 288			
				J 289			
				U 290			
				J 291			
				U 292			
				J 293			
				U 294			
				J 295			
				U 296			
				J 297			
				U 298			
				J 299			
				U 300			
				J 301			
				U 302			
				J 303			
				U 304			
				J 305			
				U 306			
				J 307			
				U 308			
				J 309			
				U 310			
				J 311			
				U 312			
				J 313			
				U 314			
				J 315			
				U 316			
				J 317			
				U 318			
				J 319			
				U 320			
				J 321			
				U 322			
				J 323			
				U 324			
				J 325			
				U 326			
				J 327			
				U 328			
				J 329			
				U 330			
				J 331			
				U 332			
				J 333			
				U 334			
				J 335			
				U 336			
				J 337			
				U 338			
				J 339			
				U 340			
				J 341			
				U 342			
				J 343			
				U 344			
				J 345			
				U 346			
				J 347			
				U 348			
				J 349			
				U 350			
				J 351			
				U 352			
				J 353			
				U 354			
				J 355			
				U 356			
				J 357			
				U 358			
				J 359			
				U 360			
				J 361			
				U 362			
				J 363			
				U 364			
				J 365			
				U 366			
				J 367			
				U 368			
				J 369			
				U 370			
				J 371			
				U 372			
				J 373			
				U 374			
				J 375			
				U 376			
				J 377			
				U 378			
				J 379			
				U 380			
				J 381			
				U 382			
				J 383			
				U 384			
				J 385			
				U 386			
				J 387			
				U 388			
				J 389			
				U 390			
				J 391			
				U 392			
				J 393			
				U 394			
				J 395			
				U 396			
				J 397			
				U 398			
				J 399			
				U 400			
				J 401			
				U 402			
				J 403			
				U 404			
				J 405			
				U 406			
				J 407			
				U 408			
				J 409			
				U 410			
				J 411			
				U 412			
				J 413			
				U 414			
				J 415			
				U 416			
				J 417			
				U 418			
				J 419			

BGS Reference: SU77SW621
British National Grid:

SU77SW 621

Date 10th September 1986		British Geological Survey		0.60 x 1.50m Bearing → 116°	
Level 36.40m.O.D.		73229 73854			

A		B		C		D	
GL		(1)				GL	
10		(2)				10	
20		(3)				20	
30		(4)				30	
40		(5)				40	
End of Trial Pit							

Samples		Strata		Test Depth m	Cu kN/m ²	Remarks
Depth	Type	No.	Description			
0.40	D	1	MADE GROUND: Firm light brown and greyish black very sandy silty clay with topsoil.			
0.80	BD	2	Soft light brown silty CLAY occasionally dessicated in parts with many shells. (Alluvium)			
1.50	BD	2	Very soft light greenish grey very silty CLAY iron stained with carbonaceous inclusions and shells. (Alluvium)			
2.20	D	4	Very soft brown slightly sandy SILT with shells and occasional gravel. (Alluvium)			
3.00	B	5	Light brown fine to coarse gravelly silty chalky fine to coarse SAND. (Alluvium)			

Plant	JCB 3CX	Water	0.70m slight seepage 3.5m moderate ingress	Cu-Approximate value of un-drained shear strength from hand vane
Shored to		Stability	Collapsing in sands on all sides	

Trial Pit Record exploration associates	Project A329(M) Broken Brow and North Earley Link Royal County of Berkshire	Contract E6043
		Trial Pit 14

BGS Reference: SU77SW324
British National Grid:

SU 77 SW 324 [7325 7385]

Contract: Reading Cross Town Stage II				Borehole No. 28				
Client: Berkshire County Council				Sheet No. 01 of 2 Depth 0 to 10 metres.				
Equipment and Methods Light Cable Percussion Boring		Ground Level : 35.95 m.O.D.		Job Number : S39/655				
Orientation : Vertical		Coordinates :		Location :				
				Dates : 12/10/89 13/10/89				
Daily Prog.	Water Levels	Remarks	In Situ Tests	Samples Taken	Depth (Thick)	Reduced Level	Description	Legend
				J 49	0.00	35.95	MADE GROUND (black dark brown soft clayey fill)	
				J 50	0.40	35.55	Soft brown silty CLAY (possibly made ground)	
				U 51	1.40			
				J 52				
				J 53				
	13/10			J 54	1.80	34.15	Very soft grey silty CLAY with traces of decaying organic matter	
				U 55				
	12/10			J 57	1.20			
				J 58				
				J 59	3.00	32.95	Coarse GRAVEL and cobbles in a matrix of chalk and soft silty CLAY	
		Waterlevel rose to 2.40m in 20 minutes		U 60				
				J 61	10.80			
				B 62	3.80	32.15	Stiff becoming weak white rubbly becomes blocky CHALK with frequent flints. orange staining at upper levels.	
				J 63				
				U 64				
				J 65				
				B 66				
				J 67				
				B 68				
				U 69				
				J 70				
				J 71				
				B 72				
			S 36	J 73				
				J 74				
				B 75				
				U 77	16.70			
				J 78				
	12/10		S 55	J 76				
				J 79				
				J 80				
				U 81				
				J 82				
				J 83				
					10.00			
Continued								
Operator JC		General Remarks: Permeability test made at 5.00m Piezometer installed at 5.0m					Appendix 1	
Scale 10m/sheet							Sheet No. 116	

5477SW/324

Contract: Reading Cross Town Stage II				Borehole No. 28				
Client: Berkshire County Council				Sheet No. 28 of 28 Depth 10 to 20 metres.				
Equipment and Methods Light Cable Percussion Boring		Ground Level : 35.95 m.O.D.		Job Number : S39/655				
Orientation : Vertical		Coordinates :		Location :				
				Dates : 12/10/89 13/10/89				
Daily Prog.	Water Levels	Remarks	In Situ Tests	Samples Taken	Depth (Thick)	Reduced Level	Description	Legend
13/10			S 92	J 84	10.00 (6.70) 10.50	25.45	Stiff becoming weak white rubbly becomes blocky CHALK with frequent flints, orange staining at upper levels. End of Borehole	
Operator JC			General Remarks: Permeability test made at 5.00m Piezometer installed at 5.0m				Appendix 1	
Scale 10m/sheet							Sheet No 117	

BGS Reference: SU77SW620
British National Grid:

Date		10th September 1986		SU77SW 620		0.60 x 1.50m		Bearing		256°																																				
Level		36.48m.O.D.		73281 73857																																										
<table border="1"> <thead> <tr> <th>Depth (m)</th> <th>Strata</th> <th>Test Depth (m)</th> <th>Cu (kN/m²)</th> <th>Remarks</th> </tr> </thead> <tbody> <tr> <td>0.0</td> <td>(1) TOPSOIL.</td> <td></td> <td></td> <td></td> </tr> <tr> <td>0.50</td> <td>(2) Firm brown slightly sandy silty CLAY. (Alluvium)</td> <td></td> <td></td> <td></td> </tr> <tr> <td>1.00</td> <td>(3) Soft to firm light brown slightly sandy silty CLAY with occasional fine chalk gravel. (Alluvium)</td> <td></td> <td></td> <td></td> </tr> <tr> <td>1.50</td> <td>(4) Soft blue green slightly sandy silty CLAY with occasional gravel and intact shells. (Alluvium)</td> <td></td> <td></td> <td></td> </tr> <tr> <td>2.00</td> <td>(5) Soft light brown very sandy very organic SILT with some fine to coarse sub-rounded to sub-angular gravel. (Alluvium)</td> <td></td> <td></td> <td></td> </tr> <tr> <td></td> <td>(6) Grade VI putty CHALK (200mm) overlying white mottled yellow brown rubbly CHALK (Grade IV). (Upper Chalk)</td> <td></td> <td></td> <td></td> </tr> </tbody> </table>												Depth (m)	Strata	Test Depth (m)	Cu (kN/m²)	Remarks	0.0	(1) TOPSOIL.				0.50	(2) Firm brown slightly sandy silty CLAY. (Alluvium)				1.00	(3) Soft to firm light brown slightly sandy silty CLAY with occasional fine chalk gravel. (Alluvium)				1.50	(4) Soft blue green slightly sandy silty CLAY with occasional gravel and intact shells. (Alluvium)				2.00	(5) Soft light brown very sandy very organic SILT with some fine to coarse sub-rounded to sub-angular gravel. (Alluvium)					(6) Grade VI putty CHALK (200mm) overlying white mottled yellow brown rubbly CHALK (Grade IV). (Upper Chalk)			
Depth (m)	Strata	Test Depth (m)	Cu (kN/m²)	Remarks																																										
0.0	(1) TOPSOIL.																																													
0.50	(2) Firm brown slightly sandy silty CLAY. (Alluvium)																																													
1.00	(3) Soft to firm light brown slightly sandy silty CLAY with occasional fine chalk gravel. (Alluvium)																																													
1.50	(4) Soft blue green slightly sandy silty CLAY with occasional gravel and intact shells. (Alluvium)																																													
2.00	(5) Soft light brown very sandy very organic SILT with some fine to coarse sub-rounded to sub-angular gravel. (Alluvium)																																													
	(6) Grade VI putty CHALK (200mm) overlying white mottled yellow brown rubbly CHALK (Grade IV). (Upper Chalk)																																													
Plant		JCB 3CX	Water	1.50m slight seepage 3.20m moderate ingress		Cu-Approximate value of un-drained shear strength from hand vane																																								
Shored to		4.00m	Stability	Unstable in face A in silt and all four sides in basal silt																																										
Trial Pit Record				Project				Contract		E6043																																				
exploration associates				A329(M) Broken Brow and North Earley Link Royal County of Berkshire				Trial Pit		13																																				

BGS Reference: SU77SW619
British National Grid:

Date 10th September 1986		Bearing 349°		0.60 x 1.50m		SU77SW 619 73319 73863	
Level 37.83m.O.D.							

A	B	C	D
GL	(1)	(2)	GL
10			10
20		(3)	20
30			30
40			40

End of Trial Pit
(Unable to continue due to large collapses in gravels)

Samples		Strata		Test Depth m.	Cu kN/m ²	Remarks
Depth	Type	No.	Description			
		1	TOPSOIL.			
0.50	D	3	MADE GROUND: Dark brown and brown slightly clayey fine to coarse sand with much fine to coarse sub-angular flint and sub-rounded chalk gravel.			
1.00	BD	3	MADE GROUND: Light brown fine to coarse gravelly coarse sand with occasional cobble flints tending towards gravel with depth with some weathered chalk bands.			

Plant	JCB 3CX	Water	2.60m Fast ingress	Cu - Approximate value of un-drained shear strength from hand vane
Shored to		Stability	Major collapses in gravels	

Trial Pit Record exploration associates	Project A329(M) Broken Brow and North Earley Link Royal County of Berkshire	Contract E6043 Trial Pit 12
--	--	--

BGS Reference: SU77SW603
British National Grid:

Sampling		Properties			Strata		Depth	Level	Legend		
Type	Cu kPa	W%	SPT N	Description							
				TOPSOIL			G.L.	39.17			
0.0-0.95	CB	26	19	Friable white mottled brown CHALK fragments in a silty matrix with flints (Grade IV)			0.40	38.77			
1.20	D	24									
1.50-1.95	CB	24	22								
2.20	D										
2.50-2.95	CB		17								
3.20	D										
3.50-3.95	CB	26	18								
4.20	D	28									
4.50-4.95	CB		17								
5.20	D										
5.50-5.95	CB		21								
6.20	D										
6.50-6.95	CB		21								
7.20	D	19									
7.50-7.95	CB		22	Becoming rubbly and slightly weathered with silty chalk matrix with flints (Grade III)							
8.20	D										
8.50-8.95	CB	30	25								
9.20	D	29									
9.50-9.95	CB		28								
					Continued over from 10.00m						
Drilling					Ground Water						
Type	From	To	Size	Fluid	Struck	Behaviour	Sealed	Date	Hole	Cased	Water
Shell and Auger	G.L.	20.25	0.15	-	4.50	Steady seepage		10.9.86	20.25	18.00	11.80
Remarks											
Borehole Record					Project			Contract			
					A329(M) Broken Brow and North Earley Link Royal County of Berkshire			E6043			
exploration associates								Borehole 12 Sheet 1 of 2			

Drilling		Properties			Strata		British Geological Survey					
Type	Cu kPa	W%	SPT N	Description	Depth	Level	Legend					
10.00	D			Continued from 10.00m								
11.00-11.45	CB	33	23	Rubbly slightly weathered CHALK in silty matrix with flints (Grade III)								
12.00	D	26										
12.50-12.95	CB		33									
13.50	D											
14.00-14.45	CB		24									
15.00	D	35										
15.50-15.95	CB		33	Becoming medium hard and block (Grade II)								
16.50	D											
17.00-17.45	CB		36									
18.00	D											
18.50-18.95	CB	16	40									
19.40	D	11										
19.80-20.25	CB		57									
End of Borehole					20.00	19.17						
Drilling					Ground Water							
Type	From	To	Size	Fluid	Struck	Behaviour	Sealed	Date	Hole	Cased	Water	
Remarks												
Borehole Record					Project				Contract			
					A329(M) Broken Brow and North Earley Link Royal County of Berkshire				E6043			
									Borehole			
									12			

BGS Reference: SU77SW655
British National Grid:

SU77/186

D STRATA LOG			
Geological Classification (BGS only)	Description of strata	Thickness m	Depth m
	Topsoil pebbles + clay	5.6	2.50
	Brown sand + gravel	2.50	4.00
	chalk + flints	4.00	30.00
(continue on separate page if necessary)			
Other comments (e.g. gas encountered, saline water intercepted, etc.)			

FOR OFFICIAL USE ONLY		
FILE	CONSENT NO.	NGS REF NO.
LIC NO.	PURPOSE	NRA REF NO.
DATE REC:	COPY TO:	ENTERED BY:

SOUTHERN LS THAMES EA.

268

Waterside Centre, Oracle Business
Park

SU 77/186

SU 77 SW

Owner: <u>Wokingham District Council</u>		Licence No.		Nat. Grid Ref. <u>SU 73565 73943</u>	
Occupier: <u>Waterside Centre</u>		IGS Ref. No.		Status: <u>Licensed (in Future)</u>	
Ground Level: <u>40</u> m OD		ft. OD		Aquifer: <u>Chalk</u>	
Level of Well Top: <u>40</u> m OD		ft. OD			
Rise Water Level: <u>6.52</u> m bar		ft. bar		Summary of Geological Section	
(Date <u>8/8/2000</u>) m OD		ft. OD		Thickness	
Construction				Depth	
Depth bar	Dia.	Lithology (below well top)			
		From	To	Dia.	Type
		<u>0</u>	<u>16</u>	<u>150mm</u>	<u>Solid</u>
		<u>16</u>	<u>30</u>	<u>150mm</u>	<u>Open</u>
Abstraction Rate		Type of Pump			
<u>10m³/day</u>		Chem./Bact. Anal. YES NO			
<u>and</u>		Well Driller <u>Smith and Webb</u>			
If insufficient space has been allowed, continue in 'Notes' overleaf					

BGS Reference: SU77SW601
British National Grid: 473610, 173920

SU77SW 601
73610 73920

Sampling		Properties			Strata		Depth	Level	Legend
Type	Cu kPa	W%	SPT N	Description					
				TOPSOIL			G.L.	42.35	
0.30 0.50-0.95	D CB		14 36	Stiff brown very silty sandy gravelly CLAY with flints			0.20	42.15	
1.20 1.50-1.95	D CB		10 31	Medium dense brown slightly silty very sandy fine and medium flint GRAVEL with some thin clay lenses			1.20	41.15	
2.20 2.50-2.95	D CB		10 30						
3.20 3.50-3.95	D CB		6 32						
4.20 4.50-4.95	D CB		20 23	Rubbly occasionally friable white mottled brown silty CHALK with flints (Grade III)			4.40	37.95	
5.20 5.50-5.95	D CB		23 27						
6.20 6.50-6.95	D CB		22 30	Becoming Grade II with depth					
7.20 7.70-8.15	D CB		23 32						
				End of Borehole			8.15	34.20	

Drilling					Ground Water						
Type	From	To	Size	Fluid	Struck	Behaviour	Sealed	Date	Hole	Cased	Water
Shell and Auger	G.L.	8.15	0.15	-	DRY			9.9.86	8.15	4.50	DRY

Remarks		
Borehole Record	Project	Contract
exploration associates	A329(M) Broken Brow and North Earley Link Royal County of Berkshire	E6043
		Borehole 10 Sheet 1 of 1

APPENDIX 7

Mr Arie Zamler
Peter Brett
Caversham Bridge House
Waterman Place
Reading
RG1 8DN

22 June 2016

Your contact is: **Ross Jarvis - Environmental Protection & Nuisance**

Dear Mr Zamler

ENVIRONMENTAL INFORMATION REGULATIONS 2004
RE: Environmental Information Request: East Reading

I write with reference to your recent request for environmental information in an area of East Reading covering land for a proposed MRT scheme. A search of records held at Reading Borough Council has found the following:

We would be grateful if you could carry out a search of your records for any environmental information relating to the site, or within 250m of the site. We are particularly interested in any issues concerning:

1. The below table shows all the sites within 250m of the proposed development that have been identified as being potentially contaminated due to their former uses. There have been no intrusive investigations made under Part IIA EPA at these sites.

easting	northing	site_name	start_date	end_date	complete_yn	notes
473240	173755	Gas Works	1912-1958	2005	y	
472840	173680	Gas Works	1879-1899	2005	y	
473100	173690	Steam Laundry	1879-1899	?	y	
473140	173665	Gravel Pit	pre 1879	1879-1899	y	
472215	173580	Biscuit Factory			y	boundaries unclear
472350	173560	Extensive Sidings To Biscuit Factory	pre 1879	1931-1973	y	
472450	173900	Warehouse	1931-1973	2005	y	
473470	173910	Scar/pit	pre 1879	1958-1974	y	

The gasworks on Kenavon Drive (472695, 173614) was remediated via the planning process between 2005-2009. Site investigations carried out during this

process can be made available if deemed relevant to the proposed development.

2. The below landfill site is within 250m of the proposed development.

site_name	geology	ngr	area	perimeter	hectares	geology_pe	gaspotent	gaspot	level_1	level_2	level_3	level_4	level_5
NAPIER ROAD READING	Upper Chalk	SU 72 8 73 9	24835.16	739.871	2.484	High	Limit-Low	Limit	<25	25-50	50-250	n/a	n/a

The Council do not hold any ground gas monitoring records from the landfill.

3. Should you require information on pollution incidents please direct your enquiries to the Environment Agency at:

Environment Agency
Isis House,
Wallingford,
Oxfordshire,
OX10 8BD
Tel: 01491 832801

4. The below installations are permitted by the Council under part B of the Environmental Permitting Regulations 2015 within 250m of the proposed development.

Unloading of Petrol into Storage at Petrol Stations (PVRI&II)	Tesco Stores Limited	Tesco Service Station, Napier Road, Reading, Berkshire, RG1 8DF
---	----------------------	---

The Environment Agency hold records of larger part A installations that may be in the vicinity. The Environment Agency can be contacted using the above details.


5. The Council do not hold any records of any private water supplies within 250m of the proposed development.

The information in this letter is given on the understanding that the Council accepts no liability for the use to which it is put and gives no guarantee as to the state of the land in question.

The information given represents the position within the Environmental Health database at the date of this letter and the Council can give no guarantee as to the impact of any future events in relation to the site in question.

If you would like to discuss the contents of this letter further, I can be contacted on 0118 9372314.

Yours sincerely,

A handwritten signature in black ink, appearing to read 'R Jarvis', is positioned over a rectangular area of the document that has been redacted with a grey stippled pattern.

Ross Jarvis
Senior Technical Officer
Environmental Protection

APPENDIX 8

Arie Zamler

From: WT Enquiries <WTenquiries@environment-agency.gov.uk>
Sent: 27 June 2016 11:54
To: Arie Zamler
Subject: RE: Ref: WT14985 - Proposed MRT Scheme, East Reading
Attachments: Discharge consents within 1 km radius of SU 730 738.xlsx; Surface WQ 1990 to 1999.xlsx; Surface WQ 2000 to 2005.xlsx; Surface WQ 2006 to 2016.xlsx; Discharge consents map.pdf; Historic Landfill Sites.pdf; Deans Farm Permit Surrender.pdf; TP0266-pr.pdf; Pollution incidents within 250 m radius of SU 730 738.xlsx

Dear Arie

Thank you for your request for environmental information for a site in East Reading.

We are not aware of any contamination issues associated with this site. However, where potentially contaminating activities have previously been conducted at a site, such as chemical or fuel storage, manufacturing or other industrial processes, the applicant is advised to seek professional advice from an appropriately experienced environmental consultant.

I have searched our records and mapping systems for the information requested although you can find some environment information on our website including water abstractions: http://maps.environment-agency.gov.uk/wiyby/wiybyController?x=357683&y=355134&scale=1&layerGroups=default&ep=map&textonly=off&lang=e&topic=water_abstractions

Please find attached information on discharge consents within a kilometre of the site.

Please find attached water quality monitoring data.

There are two historic landfill sites within a 250 metre radius and I have attached a map to show the location of the sites. Deans Farm was licensed under reference WML 86148 and the license was surrendered in April 2010. Napier Road Landfill was not licensed and I have attached the information we hold on this site.

Our records show that we hold no information on waste transfer and waste treatment sites other than the waste management license for Deans Farm.

There have been no pollution incidents above a category 3 minor incident and I have attached a list of recorded incidents.

There are two permits for radiological sources but they are at the Reading University Campus at Whiteknights Road, approximately 1.5 km to the south of the site.

We are not aware of any historical ground investigation, geoenvironmental studies or remediation reports affecting the site.

I hope that we have correctly interpreted your request. Please refer to our Open Government Licence to see how you may use the supplied data: <http://www.nationalarchives.gov.uk/doc/open-government-licence/version/3/>

Did you know that many of our datasets are available online? Simply visit environment.data.gov.uk

We respond to requests for recorded information that we hold under the Freedom of Information Act 2000 (FOIA) and the associated Environmental Information Regulations 2004 (EIR).

We are committed to providing a professional customer service. Please help us understand more about what is important to you by completing on line survey:

<http://www.smartsurvey.co.uk/s/EnvironmentAgencyCustomerSurvey/?a=WT>

Please get in touch if you have any further queries or contact us within two months if you would like us to review the information we have sent.

Kind regards

Julia Hewitt
Customers and Engagement Officer

Customers and Engagement
Environment Planning and Engagement
Environment Agency
West Thames Area
Red Kite House, Howbery Park, Wallingford, OX10 8BD

Telephone: 020302 59673



You can follow us on Twitter at @EnvAgencySE

From: Arie Zamler [
Sent: 07 June 2016 10:14
To: Enquiries, Unit
Subject: Ref: 160610/RD11 Proposed MRT Scheme, East Reading - Request for Environmental Information
Importance: High

Dear Sir / Madam,

**RE: Proposed MRT Scheme, East Reading
Request for Environmental Information**

We are a company of geo-environmental and geotechnical engineers engaged to prepare a Phase 1 Desk Study for Proposed MRT Scheme, East Reading; centred on NGR SU 730 738 and shown redline boundary on the enclosed plans.

We require further environmental details for our study and kindly request that you carry out a search of your records and provide us with the locations and available details of any of the following within 250m of the sites boundaries:-

- Water abstractions
- Discharge consents
- Groundwater and surface water quality monitoring data
- Landfill sites (licensed or otherwise)
- Waste transfer & Waste treatment sites
- Recorded pollution incidents

Details of all current licenses including radiological sources in force for Part A processes
Any historical ground investigation, geoenvironmental studies and remediation reports
Any other information relating to the environmental susceptibility of the site.

We look forward to hear back from you in your earliest convenience.

Regards,

Arie Zamler
Senior Engineer

For and on behalf of Peter Brett Associates LLP
Caversham Bridge House, Waterman Place, Reading, Berkshire, RG1 8DN

w www.peterbrett.com



Privilege and Confidentiality Notice. This email from Peter Brett Associates LLP and any attachment to it are intended only for the party to whom they are addressed. They may contain privileged and, or confidential information. If you have received this transmission in error, please notify the author immediately and delete the email and any attachment. If you are not the intended recipient you must not use or disclose, print or rely on it nor on any attachment to it. You are advised that you open any attachment at your own risk.
Peter Brett Associates LLP is a limited liability partnership registered in England and Wales. Registered number: OC334398. Wren & Bell, Roger Tym & Partners, Baker Associates, Martin Wright Associates and Hannah, Reed and Associates are part of Peter Brett Associates LLP. We use the terms "Partner" and, or "Member" to refer to a member of Peter Brett Associates LLP. A list of the members is open to inspection at our registered office. Registered Office: Caversham Bridge House, Waterman Place, Reading, Berkshire, RG1 8DN. UK T: +44 (0)118 950 0761 F: +44 (0)118 959 7498. Brett Consulting Limited is wholly owned by Peter Brett Associates LLP. Registered number: 07765026. Registered address: as above.

This message has been scanned and no issues discovered.
[Click here to _____ report this email as spam](#)

Information in this message may be confidential and may be legally privileged. If you have received this message by mistake, please notify the sender immediately, delete it and do not copy it to anyone else.

We have checked this email and its attachments for viruses. But you should still check any attachment before opening it.
We may have to make this message and any reply to it public if asked to under the Freedom of Information Act, Data Protection Act or for litigation. Email messages and attachments sent to or from any Environment Agency address may also be accessed by someone other than the sender or recipient, for business purposes.
[Click here to report this email as spam](#)

This message has been scanned for viruses by Websense

—

Surrender notice with introductory note

Environmental Permitting (England & Wales) Regulations 2010

Deans Farm

Environment Agency
Redlands Pit
Caversham
Reading
Berkshire
RG4 5JZ

Surrender notice number
EPR/CP3494LR/S001

Permit number
EPR/CP3494LR

**Deans Farm,
Permit number EPR/CP3494LR**

Introductory note

This introductory note does not form a part of the permit

The following notice is issued in accordance with regulation 25 and Part 1 of Schedule 5 of The Environmental Permitting (England and Wales) Regulations 2010 (S.I.2010 No. 675) (the Regulations) to surrender a permit issued under the Regulations to operate the regulated facility.

The status log of a permit sets out the permitting history, including any changes to the permit reference number.

Status Log of the permit		
Detail	Date	Response Date
Application OCC/106 (EAWML 86148)	03/10/91	
Permit determined	01/06/92	
Surrender application EPR/CP3494LR/S001	30/07/08	
Surrender notice issued	13/04/10	

End of Introductory Note

Surrender

Environmental Permitting (England and Wales) Regulations 2010

Surrender notice

Permit number

EPR/CP3494LR

Surrender number

EPR/CP3494LR/S001

Operator

Environment Agency

Red Kite House

Howbery Park

Wallingford

OX10 8BD

Regulated Facility

Deans Farm

Redlands Pit

Caversham

Reading

Berkshire

RG4 5JZ

The Environment Agency in exercise of its powers under Regulation 25 and Part 1 of Schedule 5 of the Environmental Permitting (England and Wales) Regulations 2010 (SI 2007 No 675) accepts the surrender of this permit

This notice shall take effect from 13 April 2010

Name	Date
	13/th April 2010

Jane McNamara


Authorised on behalf of the Environment Agency

Discharge consents locations Reading

Legend

WIMS Active Discharge Consents Outlets

- Agriculture
- Miscellaneous
- Sewage Outlet - not from Water Companies
- Sewage Outlet - from Water Companies
- Sewage and Trade combined
- Trade
- Waste Site



0 130 260 390 m.




© Environment Agency copyright and / or database rights 2014. All rights reserved. © Crown Copyright and database right 2014. Ordnance Survey licence number 100024198.

Permit Number	Permit Version	Outlet Reference Number	Site Name	Address Line 1	Address Line 2	Address Line 3	Address Line 4	Post Code	Receiving Watercourse	Organisation Name	Discharge National Grid Reference	Outlet National Grid Reference	Date Issued	Date Effective	Date Revoked	Outlet Code	Outlet Description	Outlet Receiving Code	Outlet Receiving Description	
TEMP.1768	2	1	Reading, Blakes Lock	Reading	Blakes Lock	-	-		Holly Brook	THAMES WATER UTILITIES LTD	SU7270073400	SU7270073400	03-Sep-10	03-Sep-10		S	Sewage - water company		1 Freshwater river	
CNTW.0610	1	1	TESCO SUPERSTORE, KINGS MEADOW, REA	TESCO SUPERSTORE, KINGS MEADOW,	READING, BERKSHIRE	-	-		RIVER THAMES	TESCO STORES LIMITED	SU7275074020	SU7275074020	19-Jul-90	19-Jul-90		D	Miscellaneous		1 Freshwater river	
TEMP.1769	2	1	Reading, Caversham	Reading	Caversham	-	-		Thames	THAMES WATER UTILITIES LTD	SU7280074500	SU7280074500	03-Sep-10	03-Sep-10		S	Sewage - water company		1 Freshwater river	
Remove																				

Historic Landfill Reading

Legend

 Historic Landfill Sites



0 130 260 390 m.



© Environment Agency copyright and / or database rights 2014. All rights reserved. © Crown Copyright and database right 2014. Ordnance Survey licence number 100024198.

Notification Identifier	Notification Date	EA Water Management Region	EA Water Management Region	EA Public Fae Region	EA Public Fae Area	Location	County	Unitary Authority	District Authority	National Grid Reference	Easting	Northing	Environment at Protection Incident	Substantiated	Incident Status	Air - Incident Category	Land - Incident Category	Water - Incident Category	Type of cause	Cause of incident	Type of premises	Premises	Type of Agricultural premises	Category of pollutant	Pollutant
87630	26-Jun-06	Thames Region	West - Thames	Thames Region	West	Cholmeley Road, Reading		READING		SU 73026 73673	473026	173673	Yes	Yes	Closed	Category 4 (No Impact)	Category 4 (No Impact)	Category 3 (Minor)	Cause Not Identified	Not Identified				Sewage Materials	Crude Sewage
337431	11-Aug-06	Thames Region	West - Thames	Thames Region	South East	Reading (Berkshire)		WOKINGHAM		SU 73136 73871	473136	173871	Yes	Yes	Closed	Category 4 (No Impact)	Category 4 (No Impact)	Category 3 (Minor)	Cause Not Identified	Not Identified				Oils and Fuel	Unidentified Oil
71997	16-Apr-06	Thames Region	West - Thames	Thames Region	West	Cholmeley Road, Reading		READING		SU 73012 73677	473012	173677	Yes	Yes	Closed	Category 4 (No Impact)	Category 4 (No Impact)	Category 3 (Minor)	Cause Not Identified	Not Identified				Oils and Fuel	Gas and Fuel Oils
123096	26-Nov-06	Thames Region	West - Thames	Thames Region	West	Cholmeley Road, Reading		READING		SU 73015 73684	473015	173684	Yes	Yes	Closed	Category 4 (No Impact)	Category 4 (No Impact)	Category 3 (Minor)	Containment Failure or Overflow	Sewer Failure or Overflow				Sewage Materials	Grey Water
1406924	29-Jan-16	South East Region	West Thames			New Town, Reading		READING		SU 72997 73676	472997	173676	Yes	Yes	Closed	Category 4 (No Impact)	Category 4 (No Impact)	Category 4 (No Impact)	Containment Failure or Overflow	Sewer Failure or Overflow	Water Industry	Foul Sewer		Sewage Materials	Crude Sewage
513893	16-Jul-06	Thames Region	West - Thames	Thames Region	West	New Town		READING		SU 73014 73699	473014	173699	Yes	Yes	Closed	Category 4 (No Impact)	Category 4 (No Impact)	Category 3 (Minor)	Unauthorised Activity	Unauthorised Discharge or Disposal				Oils and Fuel	Other Oil or Fuel

Environment Agency - Thames West Area
Database Extract

SiteName: NAPIER ROAD

District: READING

GridRef: SU 728 739

Status: CLOSED

Landowner:

Operator:

WasteCategories: B

Licence: NO LICENCE

Monitoring:

General:

FileNumber:

Geology: GRAVEL

Waste Categories

A: Inert materials (soil, brick, concrete, glass, clay, sand etc.)

B: Semi-inert materials (wood, paper, cardboard, plasterboard, plastic, etc.)


C: Biodegradable wastes (food, sewage sludge, household, garden etc.)

D: Difficult wastes (e.g. tyres, sludges)

E: Special wastes (hazardous chemical wastes, asbestos)

Napier Road, Reading

This map is reproduced from the OS map by the Environment Agency with the permission of the Controller of Her Majesty's Stationery Office, Crown Copyright. Unauthorised reproduction infringes Crown Copyright and may lead to prosecution or civil proceedings: Licence Number GD 03177G



SURVEY OF LANDFILL SITES

Site NAPIER ROAD READING

Grid Ref 501 728 730

Weather & Ground Conditions DRY

Topography LEVEL

Slumping NO

Winter Waterlogging NO

Surface Cracks NO

Visible Waste NO

Impermeable Cap NO

Soil Cover YES

Vegetation MINIMAL

Vegetation Stress NO

Odour NO

Gas Bubbles NO

Buildings BUILDING WORK IN PROGRESS

Barometric Pressure Start

Finish

Notes

UNABLE TO SURVEY SITE BECAUSE OF BUILDING
WORK SURVEY TO BE CARRIED OUT WHENEVER ABLE.

NAPIER ROAD

SU 728 739

TP0266



APPENDIX 9

Receptor	Sensitivity Value or 0 if not present	Pathway	Present (Y=1, N=0)	EPH & Solvents	PAHs	Metals	Asbestos	Biocides	Permanent Gases	Consequence (Hazard Classification x Sensitivity)	Probability/ Likelihood	Estimated Risk
Human Health - On-Site Current Users	5	Ingestion of fruit or vegetable leaf or roots	0	x	x	√	x	√	x	N/A	N/A	N/A
		Ingestion of contaminated drinking water	0	√	√	x	x	√	x	N/A	N/A	N/A
		Ingestion of water / sediments when swimming	1	√	√	√	√	√	x	Medium	Unlikely	Low
		Ingestion of soil/dust indoors	0	√	√	√	√	√	x	N/A	N/A	N/A
		Ingestion of soil/dust outdoors	1	√	√	√	√	√	x	Medium	Unlikely	Low
		Inhalation of particles (dust / soil) indoor and outdoor	1	√	√	√	√	√	x	Medium	Unlikely	Low
		Inhalation of vapours/gases – outdoor	1	√	x	x	x	x	√	Medium	Unlikely	Low
		Inhalation of vapours/gases - indoor	0	√	x	x	x	x	√	N/A	N/A	N/A
		Dermal absorption via direct contact with soil	1	√	√	√	√	√	x	Medium	Unlikely	Low
		Dermal absorption via waters (swimming / showering)	1	√	√	√	√	√	x	Medium	Unlikely	Low
Human Health On-Site Future User	5	Ingestion of fruit or vegetable leaf or roots	0	x	x	√	x	√	x	N/A	N/A	N/A
		Ingestion of contaminated drinking water	0	√	√	x	x	√	x	N/A	N/A	N/A
		Ingestion of water / sediments when swimming	1	√	√	x	x	√	x	Medium	Unlikely	Low
		Ingestion of soil/dust indoors	0	√	√	√	√	√	x	N/A	N/A	N/A
		Ingestion of soil/dust outdoors	1	√	√	√	√	√	x	Medium	Unlikely	Low
		Inhalation of particles (dust / soil) indoor and outdoor	1	√	√	√	√	√	x	Medium	Unlikely	Low
		Inhalation of vapours – outdoor	1	√	x	x	x	x	√	Medium	Unlikely	Low
		Inhalation of vapours - indoor	0	√	x	x	x	x	√	N/A	N/A	N/A
		Dermal absorption via direct contact with soil	1	√	√	√	√	√	x	Medium	Unlikely	Low
		Dermal absorption via waters (swimming / showering)	1	√	√	√	√	√	x	Medium	Unlikely	Low
Human Health - Neighbours	5	Ingestion of fruit or vegetable leaf or roots	0	x	x	√	x	√	x	N/A	N/A	N/A
		Ingestion of contaminated drinking water	1	√	√	x	x	√	x	Medium	Unlikely	Low
		Ingestion of water / sediments when swimming	1	√	√	x	x	√	x	Medium	Unlikely	Low
		Ingestion of soil/dust indoors	1	√	√	√	√	√	x	Medium	Unlikely	Low
		Ingestion of soil/dust outdoors	1	√	√	√	√	√	x	Medium	Unlikely	Low
		Inhalation of particles (dust / soil) indoor and outdoor	1	√	√	√	√	√	x	Medium	Unlikely	Low
		Inhalation of vapours – outdoor	1	√	x	x	x	x	√	Medium	Unlikely	Low
		Inhalation of vapours - indoor	1	√	x	x	x	x	√	Medium	Unlikely	Low
		Dermal absorption via direct contact with soil	1	√	√	√	√	√	x	Medium	Unlikely	Low
		Dermal absorption via waters (swimming / showering)	1	√	√	√	√	√	x	Medium	Unlikely	Low
Human Health - Construction/ Maintenance Workers*	4	Ingestion of soil/dust indoors	0	√	√	√	√	√	x	N/A	N/A	N/A
		Ingestion of soil/dust outdoors	1	√	√	√	√	√	x	Medium	Likely	Moderate
		Inhalation of particles (dust / soil) outdoor	1	√	√	√	√	√	x	Medium	Likely	Moderate
		Inhalation of vapours – outdoor	1	√	x	x	x	x	√	Medium	Likely	Moderate
		Inhalation of vapours - indoor	0	√	x	x	x	x	√	N/A	N/A	N/A
		Dermal absorption via direct contact with soil	1	√	√	√	√	√	x	Medium	Likely	Moderate
Groundwater (Shallow)	3	Leaching	1	√	√	√	√	√	x	Mild	Low	Low
		Migration via natural or anthropogenic	1	√	√	√	√	√	√	Mild	Low	Low
Groundwater (Deep)	5	Leaching	1	√	√	√	√	√	x	Medium	Low	Moderate
		Migration via natural or anthropogenic	1	√	√	√	√	√	√	Medium	Low	Moderate
Surface Water	5	Direct runoff or discharges from pipes	1	√	√	√	√	√	x	Medium	Low	Moderate
		Indirect via recharge from groundwater (hydraulic flow)	1	√	√	√	√	√	x	Medium	Low	Moderate
		Deposition of wind blown dust	1	√	√	√	√	√	x	Medium	Unlikely	Low
Property - Buildings	2	Direct contact	1	√	√	x	x	x	x	Mild	Low	Low
		Explosion due to gas migration via natural / anthropogenic	0	√	x	x	x	x	√	N/A	N/A	N/A
Ecological Systems	2	Direct deposition of particles / dust - wind blown or flood	1	√	√	√	√	√	x	Mild	Unlikely	Very Low
		Indirect - through watering	1	√	√	√	x	x	x	Mild	Unlikely	Very Low
		Inhalation of gases/vapours or particulates/dust by animals	1	√	√	√	x	x	√	Mild	Unlikely	Very Low
		Ingestion of of vegetation / water / soil by animals	1	√	√	√	√	√	x	Mild	Unlikely	Very Low
Property - Animal/Crop	1	Direct (including deposition via wind or flood)	1	√	√	√	√	√	x	Minor	Unlikely	Very Low
		Indirect (through watering)	1	√	√	√	x	x	x	Minor	Unlikely	Very Low
		Inhalation of gas / vapour / particulates / dust by animals	1	√	x	x	x	x	√	Minor	Unlikely	Very Low
		Ingestion of vegetation / water / soil by animals	1	√	√	√	√	√	x	Minor	Unlikely	Very Low

Risk estimation establishes the magnitude and probability of the possible consequences (what degree of harm might result and how likely).
The criteria for classifying probability and consequence are set out in Tables 3 and 4 of the PBA methodology.
Green text highlights one or more elements of the Pollutant Linkage are missing and therefore eliminated

EPH = Extractable hydrocarbons
PAHs = Poly Aromatic Hydrocarbons

 Offices throughout the UK and continental Europe www.peterbrett.com	 Reading Borough Council Working better with you	TABLE SUMMARISING POLLUTANT LINKAGES AND RISK ESTIMATION PROPOSED MRT SCHEME, EAST READING		Date		15/06/2017
				A3 Scale		nts
				Drawn		az
				Checked		rht
				Table		1