# Regulations Compliance Report

Approved Document L1A, 2013 Edition, England assessed by Stroma FSAP 2012 program, Version: 1.0.3.0
*Printed on 25 February 2016 at 09:05:16*

## Project Information:

**Assessed By:** Jonathan Ponting (STRO000148) **Building Type:** Semi-detached House

## Dwelling Details:

**NEW DWELLING DESIGN STAGE** Total Floor Area: 102.8m²

**Site Reference :** TWCPRG1 **Plot Reference:** 25 - D3 Sem

**Address :** Plot 25, Coley Park, Reading, RG1

## Client Details:

**Name:** Taylor Wimpey (West London)

**Address :**

**This report covers items included within the SAP calculations.**
**It is not a complete report of regulations compliance.**

## 1a TER and DER

Fuel for main heating system: Mains gas
Fuel factor: 1.00 (mains gas)

| | | |
|---|---|---|
| Target Carbon Dioxide Emission Rate (TER) | 16.28 kg/m² | |
| Dwelling Carbon Dioxide Emission Rate (DER) | 15.59 kg/m² | **OK** |

## 1b TFEE and DFEE

| | | |
|---|---|---|
| Target Fabric Energy Efficiency (TFEE) | 47.9 kWh/m² | |
| Dwelling Fabric Energy Efficiency (DFEE) | 43.2 kWh/m² | |
| | | **OK** |

## 2 Fabric U-values

| Element | Average | Highest | |
|---|---|---|---|
| External wall | 0.25 (max. 0.30) | 0.25 (max. 0.70) | **OK** |
| Party wall | 0.00 (max. 0.20) | - | **OK** |
| Floor | 0.17 (max. 0.25) | 0.17 (max. 0.70) | **OK** |
| Roof | 0.13 (max. 0.20) | 0.22 (max. 0.35) | **OK** |
| Openings | 1.40 (max. 2.00) | 1.40 (max. 3.30) | **OK** |

## 2a Thermal bridging

Thermal bridging calculated from linear thermal transmittances for each junction

## 3 Air permeability

| | | |
|---|---|---|
| Air permeability at 50 pascals | 5.00 (design value) | |
| Maximum | 10.0 | **OK** |

## 4 Heating efficiency

Main Heating system: Database: (rev 387, product index 017862):
Boiler systems with radiators or underfloor heating - mains gas
Brand name: Ideal
Model: LOGIC COMBI ESP
Model qualifier: 30
(Combi)
Efficiency 89.0 % SEDBUK2009
Minimum 88.0 % **OK**

Secondary heating system: None

# Regulations Compliance Report

## 5 Cylinder insulation

| | | |
|---|---|---|
| Hot water Storage: | No cylinder | |

## 6 Controls

| | | |
|---|---|---|
| Space heating controls | Programmer, room thermostat and TRVs | OK |
| Hot water controls: | No cylinder | |
| Boiler interlock: | Yes | OK |

## 7 Low energy lights

| | | |
|---|---|---|
| Percentage of fixed lights with low-energy fittings | 100.0% | |
| Minimum | 75.0% | OK |

## 8 Mechanical ventilation

| | | |
|---|---|---|
| Continuous extract system (decentralised) | | |
| Specific fan power: | 0.16 0.16 | |
| Maximum | 0.7 | OK |

## 9 Summertime temperature

| | | |
|---|---|---|
| Overheating risk (Thames valley): | Slight | OK |

Based on:

| | |
|---|---|
| Overshading: | Very Little |
| Windows facing: North | 0.96m² |
| Windows facing: South | 2.24m² |
| Windows facing: South | 6.02m² |
| Windows facing: North | 3.65m² |
| Windows facing: North | 2.25m² |
| Windows facing: West | 2.08m² |
| Windows facing: West | 0.52m² |
| Roof windows facing: South | 1.28m² |
| Ventilation rate: | 8.00 |
| Blinds/curtains: | Dark-coloured curtain or roller blind<br>Closed 100% of daylight hours |

## 10 Key features

| | |
|---|---|
| Roofs U-value | 0.11 W/m²K |
| Party Walls U-value | 0 W/m²K |