

NOTES

IF THIS DRAWING HAS BEEN RECEIVED ELECTRONICALLY IT IS THE RECIPIENTS RESPONSIBILITY TO PRINT THE DOCUMENT TO THE CORRECT SCALE.

ALL DIMENSIONS ARE IN MILLIMETERS UNLESS STATED OTHERWISE IT IS RECOMMENDED THAT INFORMATION IS NOT SCALED OFF THIS DRAWING.


THIS DRAWING SHOULD BE READ IN CONJUNCTION WITH ALL OTHER RELEVANT DRAWINGS AND SPECIFICATIONS FORMING THE EXTENT OF THIS WORK PACKAGE.

CROSS REFERENCE SHOULD BE MADE TO ARCHITECTS & STRUCTURAL ENGINEERING DRAWINGS WHERE APPLICABLE.

THIS DRAWING SHALL BE READ IN CONJUNCTION WITH THE ARCHITECTS FIRE STRATEGY DRAWING FOR COMPARTMENTATION WHERE APPLICABLE.

NOTES:

- EQUIPOTENTIAL SOCKETS
- SUPPLEMENTARY EQUIPOTENTIAL BONDING CONNECTION POINTS FOR THE CONNECTION OF ME EQUIPMENT SHALL BE PROVIDED IN EACH GROUP 2 MEDICAL LOCATION, A MINIMUM OF FOUR SOCKETS PER PATIENT LOCATION.
- ANY ADDITIONAL SUPPLEMENTARY BONDING REQUIRED BY IET REGULATIONS 710.415.2, BUT NOT INDICATED ON THIS SCHEMATIC SHALL BE PROVIDED AND THE CONNECTION INCLUDED ON THE AS BUILT DRAWING FOR THE PROJECT.
- THE MINIMUM RESISTANCE OF THE PROTECTIVE CONDUCTOR BETWEEN THE EARTH TERMINAL OF ANY SOCKET OUTLET OR FIXED EQUIPMENT AND ANY EXTRANEIOUS CONDUCTIVE PART SHALL NOT EXCEED 0.2 OHMS.
- THE NUMBER OF EQUIPOTENTIAL BONDING BAR LINKS TO LOCAL EARTH BARS IS INDICATIVE. ACTUAL NUMBER OF EBB'S TO BE TAKEN FROM THE POWER DRAWINGS.
- EQUIPOTENTIAL BONDING BARS SHALL BE IN ACCORDANCE WITH BS7671, SECTION 710.
- HUB CABINET EARTHING TO BE CARRIED OUT IN ACCORDANCE WITH BS6701.
- EACH RACK AND FRAME IN THE HUB CABINET, TO HAVE A SEPARATE CONNECTION TO THE EARTH BAR IN THE HUB ROOM.
- HUB CABINET EARTH STUD TO BE CONNECTED TO THE EARTH BAR IN THE HUB ROOM.
- ALL METALLIC COMPONENTS WITHIN THE HUB ROOM WILL BE BONDED TO THE EARTH BAR IN THE HUB ROOM.



PO1	MAY 24	ISSUED FOR COMMENTS	FB
REV	DATE	DESCRIPTION	ISSUED BY

ISSUED FOR STAGE 2	S2
--------------------	----

SAFETY, HEALTH AND ENVIRONMENTAL INFORMATION

READERS OF THIS DRAWING:

ALL EFFORTS HAVE BEEN TAKEN BY DSSR TO DESIGN OUT SIGNIFICANT HAZARDS WITHIN THE DESIGN RISK ASSESSMENT PROCESS. IT IS OUR OPINION THAT THE HAZARDS DETAILED BELOW CANNOT BE DESIGNED OUT BY US GIVEN THE CONSTRAINTS OF THE BRIEF AND ARE HIGHLIGHTED SO THAT OTHER MEANS CAN BE DEVELOPED TO MITIGATE THE RESIDUAL RISKS IDENTIFIED.

IT IS ASSUMED THAT A COMPETENT M&E CONTRACTOR OR USER WILL BE AWARE OF THE STANDARD FORESEEABLE RISKS ASSOCIATED WITH WORKING WITH THE TYPE OF SERVICES DETAILED WITHIN THE DRAWING.

DSSR | CONSULTING ENGINEERS

Glasgow Harrogate London Manchester

Manchester Office
Tallford House
Chester Road
Sheffield
Manchester
M20 0RS

Tel: +44 (0)161 872 4811
manchester@dssr.co.uk
www.dssr.co.uk

MTX CONSULTING LTD
Innovative Design
Brook Court
Lime Works Road
Huddersfield
West Yorkshire
HD6 3JG

T: 01484 696 0225
info@mtx.co.uk
www.mtx.co.uk

PROJECT:
**Royal Berkshire Hospital
NHS Foundation Trust
Royal Berkshire Hospital Urology**

TITLE:
EARTHING SCHEMATIC

Drawn By: FB	Checked By: BH	DSSR Ref: M0364
Rev: FB	Date: MAY 24	Rev: NTS
Project - Originator - Volume - Level - Type - Role - Number	P24-0002-DSSR-XX-XX-SC-E-61203	
Project - Originator - Volume - Level - Type - Role - Number	P01	