



General Notes

1. This drawing is © copyright Hampshire County Council 2023. No unauthorised reproduction of any kind is permitted.
2. No dimensions to be scaled from this drawing. Verify all dimensions prior to construction. Immediately report any discrepancies on the document to the Architect/Contract Administrator. This document shall be read in conjunction with associated models, specifications and related consultant's documents.
3. Drawing to be read with all relevant Architectural, Interiors, Structural, M&E, Drainage/Public Health, Landscape, Civils and Interiors drawings and specifications.
4. This map is reproduced from Ordnance Survey material with the permission of Ordnance Survey on behalf of the controller of Her Majesty's Stationery Office © Crown copyright. Unauthorised reproduction infringes Crown Copyright & may lead to prosecution or civil proceedings (100019180) 2023.

Hampshire County Council



Tree to be retain and protected

Root protection area (RPA)
Calculated in accordance with Section 4.6 - BS5837:2012

Excavation to be completed by hand in accordance with paragraph 6.29. Any required root pruning to be in accordance with BS 3998. Pruning of roots over 25mmØ to be monitored by arboriculturalist with the final cut being carried out within the retained soil and the exposed cut end treated with Avengelus Pro Gel. Following treatment roots will be covered with 25mm of soil at least. Roots must not be allowed to be exposed for more than 30 mins unless covered with hessian sacking as a temporary measure. Post holes must be lined with an impermeable membrane.

After completion of works, ongoing monitoring of trees condition will be carried out by LA arboriculturalist.

Minor crown lifting may be required after consultation with arboriculturalist. Only the lowest limbs that are causing obstruction are to be removed (only limbs below 1.8m above ground level). All in accordance with paragraphs 6.13 - 6.18 of the AIA.

Proposed 1.8m boundary fencing hoop topped with matching gate

Proposed 1.2m low level fencing palisade timber hardwood posts with one vertical palisade per bay lifted at the base by 100mm to create mammal movement gaps

C2	Planning and Construction Issue	20/09/2024	JM	CL
C1	Planning and Construction Issue	12/07/2024	JM	CL

Rev	Description	Date	By	Chkd
-----	-------------	------	----	------

HCC Property Services,
Three Ministers House,
76 High Street, Winchester SO23 8UL
Tel: (01962) 847801



PROJECT NAME
E05323 - Park Lane School

SHEET NAME
Infant School
Boundary Fence Phase
Tree Protection Plan

SCALE	DRAWN	CHKD	APRV
1:700 @ A3	JM	CL	-

DRAWING No.
project code - originator - volume - level - type - role - number

E05323-HCC-DR-L-7208

SUITABILITY
code description

S3 SUITABLE FOR REVIEW & COMMENT