



Project Number	0448
Project Name	VASTERN ROAD
Project Area	READING

Filename	S:\LP2333\Project admin\07.0 Pre-tender\7.1 Landscape specifications & plant schedules\Live\Planting Schedules\0448-FIR10-XX-XX-SC-L-810-0001.xlsx\Cover Sheet	Author	Checked Date	Initials	Authorised Date	Initials
		DT	24/03/2023	AW		

[illegible]

fira landscape architecture & urban design				1st Floor, 36 Bennetts Hill, Birmingham, B2 5SN			
Job No.:	Project Name	Issue Status	Author	Checked	Date	Revision	Filename
0448	VASTERN ROAD READING	PLANNING	AW	DA	30/03/2023	P04	0448-FIR10-XX-XX-SC-L-810-0001
ABBREVIATIONS USED IN THE SCHEDULE:		T= Transplant, W= Whip, F= Feathered, HS= Half Standard, S= Standard, SS= Select Standard, HS= Heavy Standard, EHS= Extra Heavy Standard, SM= Semi Mature, MS= Multi-Stemmed, O= Open Ground, W= Root Wrapped, WRB= Wire Rootball					
Notes:		Trees should only be planted during the appropriate Season between late October and late March. Trees should NOT be planted 'out of season' unless agreed with the Landscape Architect. Trees should only be Planted while soil and weather conditions are suitable and NOT during periods of frost or strong winds					
TREE SCHEDULE - Semi-Mature							
Species	Girth and Height (cm)	Times Transplanted	Clear Stem (CS) or Feathered (F)	Classification	Notes	Quantity No.	Rate
Acer campestre	300-350	Containerised 80L	F	MS	3no stems from base	1	Specimen
Acer platanoides 'Columnare'	18-20	3x	CS	SM/WRB (900mm)		1	Specimen
Betula pendula	18-20	3x	F	SM/WRB (900mm)		3	Specimen
Carpinus betulus 'Fastigiata'	18-20	5x	F	SM/WRB (900mm)	Matching crown shape, height. Fully furnished to base. Wide spread	10	Specimen
Carpinus betulus 'Streetwise'	18-20	5x	CS	SM/WRB (900mm)		1	Specimen
Gleditsia triacanthos 'Skyline'	20-25	4x	CS	SM/WRB (900mm)	Avenue matching crown shape/height and clear stem	10	Specimen
Gingko biloba	30-35	4x	CS	SM/WRB (900mm)	Avenue matching crown shape height and clear stem	1	Specimen
Liquidambar styraciflua	18-20	3x	CS	SM/WRB (900mm)	Matching shape - full crown imposing tree	2	Specimen

fira landscape architecture & urban design				1st Floor, 36 Bennetts Hill, Birmingham, B2 5SN			
Job No.:	Project Name	Issue Status	Author	Checked	Date	Revision	Filename
0448	VASTERN ROAD	PLANNING	AW	DA	30/03/2023	P04	0448-FIR10-XX-XX-SC-L-810-0001
	READING						
ABBREVIATIONS USED IN THE SCHEDULE:		T= Transplant, W= Whip, F= Feathered, HS= Half Standard, S= Standard, SS= Select Standard, HS= Heavy Standard, EHS= Extra Heavy Standard, SM= Semi Mature, MS= Multi-Stemmed, O= Open Ground, W= Root Wrapped, WRB= Wire Rootball					
Notes:		Trees should only be planted during the appropriate Season between late October and late March. Trees should NOT be planted 'out of season' unless agreed with the Landscape Architect. Trees should only be Planted while soil and weather conditions are suitable and NOT during periods of frost or strong winds					
TREE SCHEDULE - Semi-Mature							
Species	Girth and Height (cm)	Times Transplanted	Clear Stem (CS) or Feathered (F)	Classification	Notes	Quantity No.	Rate
Liquidambar styraciflua	20-25	4x	CS	SM/WRB (900mm)	Matching shape - full crown imposing tree	6	Specimen
Platanus x hispanica	40-45	5x	CS	SM/WRB (1200mm)	Avenue matching crown shape/height	3	Specimen
Prunus sargentii 'Rancho'	18-20	4x	CS	SM/WRB	Avenue matching crown shape/height and clear stem - straight stem	2	Specimen
Quercus robur	30-35	4x	CS	SM/WRB	Avenue matching crown shape/height and clear stem	2	Specimen
Sorbus aucuparia 'Asplenifolia'	18-20	4x	F	SM/WRB	Specimen fully finished to ground level	4	Specimen
Tilia cordata 'Corzam'	18-20	4x	CS	SM/WRB	Avenue matching crown height shape and clear stem	5	Specimen
Tilia cordata 'Greenspire'	18-20	4x	CS	SM/WRB	Avenue matching crown height shape and clear stem	1	Specimen
Tilia cordata 'Greenspire'	20-25	4x	CS	SM/WRB	Avenue matching crown height shape and clear stem	1	Specimen

fira landscape architecture & urban design				1st Floor, 36 Bennetts Hill, Birmingham, B2 5SN				
Job No.:	Project Name	Issue Status	Author	Checked	Date	Revision	Filename	
0448	VASTERN ROAD	PLANNING	AW	DA	30/03/2023	P04	0448-FIR10-XX-XX-SC-L-810-0001	
	READING							
ABBREVIATIONS USED IN THE SCHEDULE:		T= Transplant, W= Whip, F= Feathered, HS= Half Standard, S= Standard, SS= Select Standard, HS= Heavy Standard, EHS= Extra Heavy Standard, SM= Semi Mature, MS= Multi-Stemmed, O= Open Ground, W= Root Wrapped, WRB= Wire Rootball						
Notes:		Trees should only be planted during the appropriate Season between late October and late March. Trees should NOT be planted 'out of season' unless agreed with the Landscape Architect. Trees should only be Planted while soil and weather conditions are suitable and NOT during periods of frost or strong winds						
TREE SCHEDULE - Semi-Mature								
Species		Girth and Height (cm)	Times Transplanted	Clear Stem (CS) or Feathered (F)	Classification	Notes	Quantity No.	Rate
Tilia cordata 'Greenspire'		30-35	4x	CS	SM/WRB	Avenue matching crown height shape and clear stem	2	Specimen
Ulmus 'New Horizon'		20-25	4x	CS	SM/WRB	Avenue matching crown height shape and clear stem	3	Specimen