

Originating Office



1st Floor
36 Bennetts Hill
Birmingham
B2 5SN

Project Number	O453
Project Name	VASTERN ROAD
Project Area	READING

Specification Title	Discipline	Document	Clause No.	Ref	Rev	Q31
TREE SCHEDULE -	LA			Q31	P05	
Semi-Mature	Document Status		PLANNING			

Filename	O453-FIR10-XX-XX-SC-L-810-0001	Author	Checked Date	Initials	Authorised Date	Initials
		DT	24/03/2023	AW	24/03/2023	RS

Revisions							
Rev	Date	Description/Details	Author	Checked Date	Initials	Authorised Date	Initials
P01	24/03/2023	Issue for Planning	DT	24/03/2023	AW	RS	24/03/2023
P02	17/06/2024	DRAFT P02 ISSUE	AW	17/06/2024	RS	RS	17/06/2024
P03	26/09/2024	P03 ISSUE	AW	26/09/2024	RS	RS	26/09/2024
P04	10/10/2024	P04 ISSUE	AW	10/10/2024	JP	RS	10/10/2024
P05	20/03/2025	P05 ISSUE	EO	20/03/2025	RS	RS	20/03/2025

fira landscape architecture & urban design				1st Floor, 36 Bennetts Hill, Birmingham, B2 5SN			
Job No.:	Project Name	Issue Status	Author	Checked	Date	Revision	Filename
O453	VASTERN ROAD	PLANNING	EO	RS	20/03/2025	P05	O453-FIR10-XX-XX-SC-L-810-0001
	READING						
ABBREVIATIONS USED IN THE SCHEDULE:		T= Transplant, W= Whip, F= Feathered, HS= Half Standard, S= Standard, SS= Select Standard, HS= Heavy Standard, EHS= Extra Heavy Standard, SM= Semi Mature, MS= Multi-Stemmed, O= Open Ground, W= Root Wrapped, WRB= Wire Rootball					
Notes:		Trees should only be planted during the appropriate Season between late October and late March. Trees should NOT be planted 'out of season' unless agreed with the Landscape Architect. Trees should only be Planted while soil and weather conditions are suitable and NOT during periods of frost or strong winds					
TREE SCHEDULE - Semi-Mature							
Species	Girth and Height (cm)	Times Transplanted	Clear Stem (CS) or Feathered (F)	Classification	Notes	Quantity No.	Rate
Acer platanoides 'Columnare'	18-20 450-650	3x	CS	SM/WRB (900mm)		1	Specimen
Betula pendula	18-20 450-500	3x	F	SM/WRB (900mm)		3	Specimen
Carpinus betulus 'Fastigiata'	18-20 450-500	5x	F	SM/WRB (900mm)	Matching crown shape, height. Fully furnished to base. Wide spread	9	Specimen
Carpinus betulus 'Lucas'	18-20 450-500	5x	F	SM/WRB (900mm)	Matching crown shape, height. Fully furnished to base. Wide spread	5	Specimen
Carpinus betulus 'Streetwise'	18-20 450-500	5x	CS	SM/WRB (900mm)		1	Specimen
Ginkgo biloba	30-35 550-600	4x	CS	SM/WRB (900mm)	Avenue matching crown shape height and clear stem. Clear single leader	1	Specimen
Gleditsia triacanthos 'Skyline'	20-25 500-550	4x	CS	SM/WRB (900mm)	Avenue matching crown shape/height and clear stem	9	Specimen

fira landscape architecture & urban design				1st Floor, 36 Bennetts Hill, Birmingham, B2 5SN				
Job No.:	Project Name	Issue Status	Author	Checked	Date	Revision	Filename	
O453	VASTERN ROAD	PLANNING	EO	RS	20/03/2025	P05	O453-FIR10-XX-XX-SC-L-810-0001	
	READING							
ABBREVIATIONS USED IN THE SCHEDULE:		T= Transplant, W= Whip, F= Feathered, HS= Half Standard, S= Standard, SS= Select Standard, HS= Heavy Standard, EHS= Extra Heavy Standard, SM= Semi Mature, MS= Multi-Stemmed, O= Open Ground, W= Root Wrapped, WRB= Wire Rootball						
Notes:		Trees should only be planted during the appropriate Season between late October and late March. Trees should NOT be planted 'out of season' unless agreed with the Landscape Architect. Trees should only be Planted while soil and weather conditions are suitable and NOT during periods of frost or strong winds						
TREE SCHEDULE - Semi-Mature								
Species		Girth and Height (cm)	Times Transplanted	Clear Stem (CS) or Feathered (F)	Classification	Notes	Quantity No.	Rate
Liquidambar styraciflua 'Worplesdon'		20-25 500-550	4x	CS	SM/WRB (900mm)	Matching shape - full crown imposing tree	6	Specimen
Platanus x hispanica		40-45 450+	5x	CS	SM/WRB (1200mm)	Avenue matching crown shape/height	3	Specimen
Prunus sargentii 'Rancho'		18-20 450-650	4x	CS	SM/WRB	Avenue matching crown shape/height and clear stem - straight stem	2	Specimen
Quercus robur		30-35 600-650	4x	CS	SM/WRB	Avenue matching crown shape/height and clear stem	1	Specimen
Sorbus aucuparia 'Aspleniifolia'		18-20 450+	4x	F	SM/WRB	Specimen fully finished to ground level	5	Specimen
Tilia cordata 'Corzam'		18-20 450+	4x	CS	SM/WRB	Avenue matching crown height shape and clear stem	5	Specimen
Tilia cordata 'Greenspire'		20-25 500-550	4x	CS	SM/WRB	Avenue matching crown height shape and clear stem	1	Specimen

fira landscape architecture & urban design				1st Floor, 36 Bennetts Hill, Birmingham, B2 5SN				
Job No.:	Project Name	Issue Status	Author	Checked	Date	Revision	Filename	
O453	VASTERN ROAD	PLANNING	EO	RS	20/03/2025	P05	O453-FIR10-XX-XX-SC-L-810-0001	
	READING							
ABBREVIATIONS USED IN THE SCHEDULE:		T= Transplant, W= Whip, F= Feathered, HS= Half Standard, S= Standard, SS= Select Standard, HS= Heavy Standard, EHS= Extra Heavy Standard, SM= Semi Mature, MS= Multi-Stemmed, O= Open Ground, W= Root Wrapped, WRB= Wire Rootball						
Notes:		Trees should only be planted during the appropriate Season between late October and late March. Trees should NOT be planted 'out of season' unless agreed with the Landscape Architect. Trees should only be Planted while soil and weather conditions are suitable and NOT during periods of frost or strong winds						
TREE SCHEDULE - Semi-Mature								
Species		Girth and Height (cm)	Times Transplanted	Clear Stem (CS) or Feathered (F)	Classification	Notes	Quantity No.	Rate
Tilia cordata 'Greenspire'		30-35 600-650	4x	CS	SM/WRB	Avenue matching crown height shape and clear stem	3	Specimen
Ulmus 'New Horizon'		20-25 500+	4x	CS	SM/WRB	Avenue matching crown height shape and clear stem	3	Specimen