

PLANTING NOTES

1. Implementation of soft landscape proposals to be undertaken following completion of main construction works during the 1st available planting season (October to March).
2. Plant material to conform to the National Plant Specification. All plant stock to originate from within the UK. All plant stock, plant handling and planting to be undertaken in accordance with the following British Standard Specifications and Codes of Practice:
- BS 3936:1992 Part1 Nursery Stock – Specification for trees and shrubs;
 - BS 3936:1981 Part10 Nursery Stock – Specification for ground cover plants;
 - BS 4428:1989 – Code of Practice for General Landscape Operations (excluding hard surfaces);
 - BS 8545:2014 – Trees from Nursery to Independence in the landscape – Recommendations; and
 - The Code of Practice 2002 (HTA).
3. Topsoil to be fertile with maximum 35% clay content and 5% minimum organic content, pH 5.8 - 7.5 and to be free of perennial weeds, weed seeds and contamination. Maximum stone content 20% (20mm in particle size), maximum size of stones 50mm in any direction.
- Existing topsoil to be ameliorated and/or screened, if necessary; to achieve this specification.
 - Imported topsoil to be to BS 3882: Multi-Purpose Grade, from an approved source, and to accord with the above specification.
4. No substitutes to the approved size and species of plants as shown on the plan will be made without prior written approval from the Local Planning Authority.
5. The Contractor is to ascertain the location of all sewers and services prior to carrying out any planting to avoid these routes or existing services.

PLANTING BEDS:

6. Planting beds to have a minimum depth of 450mm topsoil over 150mm broken up ground with all stones over 50mm removed. Soil conditioner: Sanitized and stabilised compost to BSI PAS 100. Apply 50mm depth even coverage and incorporate into topsoil during cultivation operations, to a minimum depth of 150mm. Compost to be Compost Association certified, or from an approved supplier conforming to this specification. If no local supplies are available alternative organic peat free compost may be specified, subject to the Landscape Architect's approval.
7. Hedgerow plants to be planted in pits 150mm wider and deeper than root spread backfilled with excavated topsoil/compost, mixed with 'Sierrablen Flora' slow release fertiliser, quantity in accordance with manufacturer's recommendations. Hedge plants to be planted in staggered rows 500 mm apart at centres specified in schedule.
8. All planting beds (apart from marginal plants) to be mulched with matured coniferous bark, with an even particle size between 15 - 65mm, to a minimum depth of 100mm over weed free soil after completion of all planting and watering operations. Bark mulch is to be free from pests, diseases, fungus and weeds; and with no fines or dust. Source and sample of bark mulch to be approved.

ONGOING MANAGEMENT AND MAINTENANCE NOTES:

1. Maintenance operations to be carried out as specified until planting becomes established (year 5 after planting).
2. Shrubs - Weed control measures to continue until canopy of shrubs is closed or for minimum period of three years to original 100mm depth of bark mulch. Weeds are to be cleared by hand or by application of translocated herbicide, with inspections made regularly through the growing season. Prune back any badly damaged shrubs to sound growth. Cut back plants adjacent to paths and access ways where necessary, retaining a balanced shape. Clear litter and debris from planted areas and cut leggy growth hard back to promote bushy growth.
3. Watering – Watering to be from above and via pipe to ensure soaking of ground until field capacity of the soils is reached. Water to occur on weekly basis during growing season (April – October) for first two years. After which, during periods of dry weather apply sufficient water to maintain healthy growth. Allow, at each operation, watering to field capacity.
4. Re-firming - Ensure that all shrubs are firmly bedded in the ground after strong winds, frost heave or other disturbances.
5. Protection/Reinstatement - Regularly inspect all planting areas, e.g. once a month, for any pest damage or vandalism/damage caused by others. Any damaged to be reported to the Employer and rectified in the next available season by replacement planting or reseedling/ turfing and protective measures if required.

PLANTING SCHEDULE

SHRUBS / HERBACEOUS/GROUND COVER PLANTING				
Abbr.	Species	Type/Size (cm)		Centres
EFD	Euonymus fortunei 'Darts Blanket'	2L Pot	20 – 30 cm	450
ESQ	Euonymus fortunei 'Silver Queen'	2L Pot	20 – 30 cm	450
HGO	Hebe 'Great Orme'	3L Pot	30 – 40 cm	600
HHP	Hebe pinnatifolia 'Pagel'	2L Pot	20 – 30 cm	450
HHH	Hedera helix 'Hibernica'	1L Pot	20 – 30 cm	450
LOP	Lonicera pileata	3L Pot	30 – 40 cm	600
SKR	Skimmia japonica 'Rubella'	3L Pot	40 – 60 cm	500
STB	Stachys byzantina	1 – 2L Pot	15 – 20 cm	500
VID	Viburnum davidii	3L Pot	20 – 30 cm	500
HEDGE PLANTING				
Planted in 2 rows 600mm apart and at staggered centres 500mm apart				
Abbr.	Species	Type/Size (cm)		Centres
ERH	Escallonia 'Red Hedger'	3L Pot	40 – 60 cm	600
NOTE:				
Pot = Container grown plants				
TS 1+1 = Transplant / Years				

KINGS ROAD

56 CHURCH

60

62

1 TO 16
OYSTER WHARF

Services trench
for
Electric/water &
BT (no gas)

Foul drainage

Surface water
drainage

RIVER KENNET

Note: Drawing remains the property of David Williams Landscape Consultancy and should not be copied without prior written consent.

Revision	Date	Initial
LEGEND		
	EXISTING TREE / VEGETATION RETAINED	
	PROPOSED SHRUB PLANTING	
	PROPOSED HEDGEROW PLANTING	
	DRAINAGE / SERVICE ROUTES	

Project:
DEVELOPMENT AT No.58 KINGS ROAD, READING RG1 3AA

Drawing Title:
LANDSCAPE PROPOSALS PLAN

Status: **PLANNING**

Date:
02-06-2025

Scale:
1:100 @ A1 size
1:200 @ A3 size

Project No:
0548

Drawing No:
L1

Drawn by:
DHW

Revision:

David Williams
Landscape
Consultancy

NORTH

Dyers
East Putford
Holsworthy
Devon
EX22 7UG

e: david.williams@dwlc.co.uk
t: (01409) 240 278 m: (07826) 270 368
www.dwlc.co.uk