

Softworks Key

- Indicative position of existing trees**
Refer to Arboricultural Impact Assessment and Arboricultural Method Statement by Hampshire Highways Arboriculture.
- Proposed multistem tree**
To be anchored with underground guying system with irrigation ring.
- Proposed heavy standard tree**
Trees proposed **outside** of the redline boundary to be to be double staked with tie and irrigation ring to detail.
- Root barriers are required between tree and adjacent highway / service routes once area has been surveyed.
- Ornamental Planting Bed**
with 75mm depth bark mulch to specification
- Existing Ornamental Planting Bed**
To be retained and protected where required. To be topped up with 75mm depth bark mulch.
- Root Barrier**
Plantex Root Protector by Dupont or equal and approved. To be a minimum of 2m deep and implemented to engineers and manufacturers specification.
- For detailed green roof specification refer to architects proposals.**



General Notes
Contractor must verify all dimensions, levels and existing service alignments on site before commencing any work or shop drawings. Any discrepancy concerning the drawings/quantities should be referred to the Landscape Architect immediately. Only figured dimensions to be taken from this drawing. Do not scale off this drawing. All landscape drawings to be read in conjunction with the landscape specification and all relevant engineer's and architect's drawings/specifications. Drawings should not be used to tender from without confirmation from the Landscape Architect. This drawing is Copyright and must not be reproduced without consent of Guarda Ltd.

C01 02/07/25	First Issue	JH	CX
Rev	Date	Comments	Dr

guarda
landscape

Suite F, Second Floor, Queens House,
123-129 Queens Road, Norwich, NR1 3PL
+44 (0)1206 638085 - www.guardalandscape.com

Client
Morgan Sindall Group
Site
Civic Offices, Reading

Drawing Title
Detailed Soft Landscaping
Proposals - Reduced scheme

Scale	1:200 @ A1	Status	CONSTRUCTION
Project	2409	Drawing Number	GUA-30-000-D-L-90110
Drawn	JH	Checked	CX
Date	July 2025		

© GUARDA Ltd. 2024